




PLAN VIEW
TWO UNIT VAULT



SECTION 'A-A'



PLAN VIEW
TWO UNIT VAULT (SPLIT VAULT)



SECTION 'B-B'

DISTRIBUTION CONSTRUCTION STANDARD
UG Transformers and Switchgears

VAULT LIGHTING ARRANGEMENT



Approved By:
I. S. 2020-02-20
Drafted By:
L. L.

Designed By:
S. K.

Original Issue:
K. S. 2009-09-08


Scale:
N. T. S.

Rev:


3

13-2200


1/3



PLAN VIEW
SINGLE UNIT VAULT - NON-URD



SECTION 'C-C'



WIRING SCHEMATIC

DISTRIBUTION CONSTRUCTION STANDARD
UG Transformers and Switchgears

VAULT LIGHTING ARRANGEMENT



Approved By:
I.S. 2020-02-20

Drafted By: L.L.
Designed By: S.K.

Original Issue:
K.S. 2009-09-08

Scale:
N.T.S.

Rev: **3**

13-2200

2/3

BOM LEGEND	
A	2 UNIT TRANSFORMER 120/208 V ROOM / VAULT
B	2 UNIT TRANSFORMER 347/600 V ROOM / VAULT
C	1-PHASE TRANSFORMER URD SYSTEM
D	3-PHASE 120/208 V TRANSFORMER URD SYSTEM
E	3-PHASE 347/600 V TRANSFORMER URD SYSTEM
F	3-PHASE 200 A SWITCH URD SYSTEM
G	3-PHASE 600 A SWITCH URD SYSTEM
H	MODULAR SWITCH
I	1 UNIT TRANSFORMER 120/208 V ROOM / VAULT
J	2 UNIT TRANSFORMER 240/416 V ROOM / VAULT
K	1 UNIT TRANSFORMER 240/416 V ROOM / VAULT
L	1 UNIT TRANSFORMER 347/600 V ROOM / VAULT

BILL OF MATERIALS FOR 13-2200

ITEM NO.	DESCRIPTION	ITEM I.D.	QUANTITY											
			A	B	C	D	E	F	G	H	I	J	K	L
1	STRAP PIPE FOR 1/2" 1 HOLE COATED	100000653	15	15	10	15	15	10	15	18	15	15	15	15
2	ANCHOR THREADED CONCRETE 1/4" X 1 1/4"	2500100	30	30	20	30	30	20	30	40	30	30	30	30
3	PANEL CIRCUIT BREAKER 70 A 120/240 V	9656560	1	1	1	1	1	1	1	1	1	1	1	1
4	BREAKER CIRCUIT 20 A 120 V	9656680	2	2	2	2	2	2	2	2	2	2	2	2
5	CABLE #12 STR CU TW75 600 V BLACK	7150100	25	25	20	25	25	20	25	25	25	25	25	25
6	CABLE #12 STR CU TW75 600 V WHITE	7150102	20	20	10	20	20	10	20	20	20	20	20	20
7	CABLE #12 STR CU TW75 600 V GREEN	7150098	20	20	10	20	20	10	20	20	20	20	20	20
8	CONDUIT PVC RIGID 1/2" IN 10' LENGTHS	5230000	5	5	5	5	5	5	6	6	5	6	5	5
9	COUPLING PVC 1/2" FOR CONDUIT	5231027	6	6	6	6	6	6	6	6	6	6	6	6
10	ADAPTER MALE PVC 1/2" FOR CONDUIT	5232000	11	13	11	11	13	11	13	12	11	13	11	11
11	BEND PVC 1/2" 90 DEG FOR CONDUIT	5233000	5	5	5	5	5	5	5	5	5	5	5	5
12	BOX UTILITY PVC 2" DEEP FOR 1/2" CONDUIT	7405002	2	2	2	2	2	2	2	2	2	2	2	2
13	BOX OCTOGON PVC 4" X 1 1/2" DEEP FOR 1/2" CONDUIT	7405003	3	3	2	3	3	3	3	3	3	4	3	3
14	LAMPHOLDER PORCELAIN 660 W 250 V KEYLESS	7440020	2	2	2	2	2	2	2	2	4	2	2	2
15	COVER PVC DUPLEX RECEPTACLE	7446000	1	1	1	1	1	1	1	1	1	1	1	1
16	COVER PVC TOGGLE SWITCH	7446002	1	1	1	1	1	1	1	2	1	2	1	1
17	TAPE PVC 3/4" X .0075" MIN LOW TEMPERATURE	7600001	1	1	1	1	1	1	1	1	1	1	1	1
18	LAMP 300 W 125/130 V PS30	8010051	2	2	2	2	2	2	2	2	4	2	2	2
19	SWITCH TOGGLE APPLIANCE 20 A 1 WAY	9653473	1	1	1	1	1	1	1	-	1	2	1	1
20	RECEPTACLE GROUND FAULT 20 A 125 V	9665648	1	1	1	1	1	1	1	1	1	1	1	1
21	LOCKNUT 1/2" CONDUIT	9655483	10	13	10	10	13	10	10	11	10	13	10	10
22	TRANSFORMER DRY TYPE 1PH 3 KVA 600-120/240 V	6621501	-	1	-	-	1	-	-	-	-	-	-	1
23	SWITCH TOGGLE APPLIANCE 20 A 3 WAY	9653472	-	-	-	-	-	-	-	2	-	-	-	-
24	CONNECTOR CU SPLIT U-BOLT #1-4/0 STR	7213000	1	1	1	1	1	1	1	1	1	1	1	1
25	CABLE #12 STR CU TW75 600 V RED	7190060	-	-	-	-	-	-	-	10	-	-	-	-
26	CEMENT SOLVENT FOR RIGID PVC CONDUIT	9652392	1	1	1	1	1	1	1	1	1	1	1	1
27	SWITCH SAFETY HEAVY DUTY 30A 600V AC	9653443	-	1	-	-	1	-	-	-	-	1	1	1
28	FUSE 600V 10A	7073017	-	2	-	-	2	-	-	-	-	-	-	2
29	TRANSFORMER DRY TYPE 1PH 3KVA 250V-120V	9662764	-	-	-	-	-	-	-	-	-	1	1	-
30	FUSE 600V 15A	9651286	-	-	-	-	-	-	-	-	-	2	2	-

* SEE NOTE 3

NOTES:

- 1) LIGHTING LAYOUTS IN THIS STANDARD ARE TO BE USED AS A GUIDELINE. LIGHTS AND ACCESORIES ARE TO BE ARRANGED TO SUIT SITE CONDITIONS.
- 2) 3 WAY TOGGLE SWITCHES SHALL BE INSTALLED NEAR EACH OF VAULT DOORS IN MODULAR SWITCHING VAULT.
- 3) QUANTITIES OF SOME MATERIALS MAY VARY DUE TO SIZE AND LAYOUT.
- 4) 1-PHASE TRANSFORMER AND 200 A SWITCH VAULT ON URD SYSTEM REQUIRES 1 LIGHT.
- 5) ALL EQUIPMENT TO BE MOUNTED ON WALLS IN URD NETWORK VAULTS.

DISTRIBUTION CONSTRUCTION STANDARD
UG Transformers and Switchgears



Approved By:
I. S. 2020-02-20
Drafted By:
L. L.
Designed By:
S. K.

Original Issue:
K. S. 2009-09-08

Scale:
N. T. S.


Rev:

3

13-2200

3/3

VAULT LIGHTING ARRANGEMENT



SERVICE TYPE	SIZE AND TYPE OF CABLE	ITEM I.D.	MIN. CONDUIT SIZE FOR 3 CONDUCTOR
13.8 kV	#1/0 3-1C TRIPLEX 15 kV AL TRXLPE	7180016	3"
13.8 kV	#3/0 3-1C TRIPLEX 15 kV Cu TRXLPE	7180020	3"
13.8 kV	500 kcmil 3-1C TRIPLEX 15 kV Cu TRXLPE	7180032	4"

NOTES:

- 1) RIGID NON-FERROUS THREADED STEEL CONDUIT TO BE USED FOR CABLE ROUTING. CONDUIT SHALL HAVE TAPERED THREAD AND BE MADE WATERTIGHT.
- 2) CONDUITS SHALL BE SECURELY ATTACHED TO HANGERS OR TO A SOLID SURFACE. THE TYPE OF SUPPORTS USED TO BE DETERMINED BASED ON FIELD CONDITIONS.
- 3) CONDUIT SIZE SHALL BE IN ACCORDANCE WITH TABLE 1 AND BE OF SUFFICIENT SIZE TO PERMIT THE CONDUCTORS TO BE DRAWN IN AND WITHDRAWN WITHOUT DAMAGE TO THE CABLES.
- 4) THE INCOMING PRIMARY SERVICE CABLES SHALL HAVE A DEDICATED CONDUIT PER RUN AND SHALL NOT BE SHARED WITH OTHER SERVICES, CONDUCTORS OR NEUTRAL.
- 5) THERE SHALL BE NO CABLE JOINTS OR SPLICES WITHIN CONDUIT.
- 6) CONDUIT SHALL BE SUPPORTED AT MAXIMUM 3000 mm (9'-10") INTERVALS AS WELL AS BEFORE AND AFTER ALL CHANGES OF DIRECTION.
- 7) CONDUIT BEND RADII AND CABLE PULLING FORCES SHALL NOT EXCEED THE LIMITS REFERENCED IN STD. 16-0220, 16-0260 AND 16-1260.
- 8) WHERE A CONDUIT ENTERS A BOX, FITTING, OR OTHER ENCLOSURE, A BUSHING SHALL BE PROVIDED TO PROTECT THE CABLE FROM ABRASION UNLESS THE DESIGN OF THE BOX, FITTING, OR ENCLOSURE IS SUCH AS TO AFFORD EQUIVALENT PROTECTION. ALL CUT ENDS SHALL BE REAMED OR OTHERWISE FINISHED TO REMOVE ROUGH EDGES.
- 9) WEATHERPROOF LABEL WILL BE AFFIXED AT REGULAR INTERVALS AROUND THE CONDUIT IN BLACK TEXT AGAINST AN ORANGE BACKGROUND THAT READS "DANGER HIGH VOLTAGE" ALONG WITH THE SYSTEM VOLTAGE, I.E. DANGER HIGH VOLTAGE 13800 V.
- 10) CONDUIT SHALL BE BONDED TO GROUND BUS OR GROUND LOOP OF INCOMING SWITCHGEAR. BONDING CABLE TO BE STRANDED BARE CU, NO SMALLER THAN #2/0, AND SECURED RELIABLY TO CONDUIT VIA MECHANICAL GROUND CONNECTOR.
- 11) IF EXPANSION JOINTS USED, BONDING JUMPERS ON CONDUIT ARE REQUIRED TO MAINTAIN CONTINUITY ACROSS JOINT.

DISTRIBUTION CONSTRUCTION STANDARD
UG Secondary and Primary Services

**TEMPORARY PRIMARY SERVICES
CONDUIT ROUTING**



Approved By:
B.L. 2018-03-01

Drafted By:
B.W.

Designed By:
B.L.

Original Issue:


Scale:
N.T.S.

Rev:

0


15-8510

1/1



NOTES:

- 1) FOUR GROUND RODS SHALL BE INSTALLED NEAR THE CORNERS OF CABLE CHAMBER.
- 2) USE #2/0 BARE COPPER CONDUCTOR FOR GROUND LOOP AND CONNECTIONS TO GROUND RODS.
- 3) ALL NEUTRALS SHALL BE CONNECTED TO GROUND LOOP.
- 4) STIRRUP SHALL BE INSTALLED WHERE SPACE IS AVAILABLE TO ALLOW FOR PROPER GROUNDING PROVISIONS.



DISTRIBUTION CONSTRUCTION STANDARD
Grounding



Approved By:
E.M. 2017-03-31

Drafted By:
B.W.

Designed By:
E.H.

Original Issue:
C.P. 2001-01-10

Scale:
N.T.S.

Rev:
4

18-5100

1/2

**UNDERGROUND SYSTEM
CABLE CHAMBER GROUNDING**



BILL OF MATERIALS FOR 18-5100			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
1	ROD 3/4" X 10' STEEL GALVANIZED	2470102	4
2	CONNECTOR 3/4" ROD TO #2/0 CU	7214200	4
3	CONNECTOR CU TERMINAL LUG TINNED #2/0 STR 1/2" HOLE	9662106	2
4	ANCHOR CONCRETE SLEEVE 1/2" X 3" LONG	9653086	2
5	WIRE #2/0 19 STR CU SD	7105160	43
6	CLIP CABLE CSA - CONDUCTOR MOUNTING	7210190	36
7	ANCHOR THREADED CONCRETE 1/4" X 1 3/4"	2500052	36
8	CONNECTOR COMPRESSION #2/0 CU TO #2/0 CU	7213156	34
9	NUT 1/2" CLAMPING C/W SPRING NUT	2520004	12
10	BOLTED PARALLEL GROOVE GROUND CLAMP	7214105	12
11	WASHER LOCK 1/2" GALV	2530116	12
12	BOLT MACHINE 1/2" X 2" C/W HEX HEAD & NUT	2510330	12
13	WASHER GALV SQUARE 1 1/2" X 1 1/2" C/W 9/16" HOLE	2530001	12
14	CONNECTOR STIRRUP GROUNDING	7251095	2
15	CONNECTOR CU U BOLT CLAMP 250-500 kcmil STR	7214413	4



* QUANTITY IS BASED ON CABLE CHAMBER SIZE 3500 mm X 4000 mm

DISTRIBUTION CONSTRUCTION STANDARD
Grounding



Approved By:
E. M. 2017-03-31

Drafted By: B. W.
Designed By: E. H.

Original Issue:
C. P. 2001-01-10

Scale:
N. T. S.


Rev: 4

18-5100


2/2

UNDERGROUND SYSTEM
CABLE CHAMBER GROUNDING





PLAN VIEW



SECTION A-A

- NOTES:**
- 1) GROUNDING SHALL BE INSTALLED AS SHOWN. RODS TO BE CONNECTED BY 2/0 BARE COPPER TO FORM A COMPLETE GROUND LOOP AROUND FOUNDATION.
 - 2) LEAVE TWO COILS EACH 2000 mm (6'-7") INSIDE EACH FOUNDATION.

DISTRIBUTION CONSTRUCTION STANDARD
Grounding

**GROUND GRID
PAD-MOUNTED EQUIPMENT**



Approved By:
V. B. 2019-05-27

Drafted By:
N. H.

Designed By:
V. B.

Original Issue:
K. S. 2012-08-30


Scale:
N. T. S.

Rev: **2**

18-5500



1/3



PLAN VIEW 
BONDING OF ADJACENT GROUND GRIDS
SEPARATED BY LESS THAN 5 m

NOTES: 

- 3) IF SEPARATION TO ANOTHER STRUCTURE IS LESS THAN 5 m, GROUNDING GRIDS SHALL BE BONDED.
- 4) IF GROUND GRIDS OVERLAP, GROUND RODS MAY BE SHARED BETWEEN GRIDS.

DISTRIBUTION CONSTRUCTION STANDARD
Grounding



Approved By:
 V.B. 2019-05-27
 Drafted By: N.H.
 Designed By: V.B.

Original Issue:
 K.S. 2012-08-30

GROUND GRID
PAD-MOUNTED EQUIPMENT

Scale:
 N.T.S.

Rev: **2**

18-5500



2/3

**MINIMUM UNDERGROUND CLEARANCES AS PER CITY OF TORONTO MCR
(EDGE TO EDGE)**

Utilities or Plant		Vertical mm (feet)	Horizontal mm (feet)	
Railways	Heavy Rail (CN/CP/GO)	Refer to STD. 31-1310		
	Light Rail (TTC/LRT/Metrolinx)	Refer to STD. 31-1200		
Hydro One	All Infrastructure	1000 (3'-4")	1000 (3'-4")	
Communication	Bell Canada	Manholes	1000 (3'-4")	
		Concrete Encased Ducts	600 (2'-0")	
		Direct Buried Ducts	300 (1'-0")	
	Others	All Infrastructure	300 (1'-0")	600 (2'-0")
Enwave Energy Corporation	Steam Pipes	600 (2'-0")	600 (2'-0")	
	Chilled Water Pipes	300 (1'-0")	300 (1'-0")	
Enbridge Gas National Energy Board	≤ NPS 300 mm (12") (Open Trench)	300 (1'-0")	600 (2'-0")	
	CER Regulated Pipelines and Vital Mains (Open Trench)	600 (2'-0")	1000 (3'-4")	
	ALL Pipelines Directional Drilling/Boring	1000 (3'-4")	1000 (3'-4")	
	Regulator Stations	Consult with City	1000 (3'-4")	
City of Toronto	Trees		See Note 1 and Std. 31-0400	
	Catch Basins		Consult with City	500 (1'-8")
	Traffic Signal Ducts		300 (1'-0")	600 (2'-0")
	Storm Sewer	< 150 (6") Dia.	150 (6")	600 (2'-0")
		150 (6") < 750 (2'-6") Dia.	300 (1'-0")	750 (2'-6")
		≥ 750 (2'-6") Dia.	500 (1'-8")	900 (3'-0")
		Maintenance Hole	-	600 (2'-0")
	Sanitary/ Combined Sewer	< 100 (4") Dia.	150 (6")	600 (2'-0")
		100 (4") < 375 (1'-3") Dia.	300 (1'-0")	750 (2'-6")
		≥ 375 (1'-3") Dia.	500 (1'-8")	900 (3'-0")
		Maintenance Hole	-	600 (2'-0")
	Water Mains	< 100 (4") Dia.	150 (6")	600 (2'-0")
		≥ 100 (4") < 400 (1'-4") Dia.	300 (1'-0")	750 (2'-6")
		≥ 400 (1'-4") Dia.	500 (1'-8")	900 (3'-0")
		Water Valve Chamber	See Note 5	600 (2'-0")
Fire Hydrant		400 (1'-4")	1500 (4'-11")	
Toronto Hydro (This to be used when other Utilities are installing their plant close to THESL infrastructure)	Poles (Direct Buried)		See Std's. 03-2400, 04-4100 and 04-5100	
	Base Mounted Poles/ Reinforced Sidewalk Bays		See Note 3	
	Cable Chamber/Vault/Tap Boxes (No Grounding Outside Structures)		-	600 (2'-0")
	Padmounts/Sub Vaults/Splice Vaults (Grounding Outside Structure)		Refer to STD. 31-4100	
	Ducts/Duct Banks		300 (1'-0")	600 (2'-0")

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

UNDERGROUND CLEARANCES



Approved by:

Drafted by:
J.D.

Designed by:
B.D.

Original issue:
J.D. 2000-12-28

Scale:
N.T.S.

Rev. 9


31-0100

1/2

Notes:

1. Any construction activity in the vicinity of trees shall be carried out in compliance with latest City of Toronto's "Tree Protection Policy and Specification for Construction Near Trees" document.
2. If the minimum clearances shown cannot be met, the subject utilities approval may be obtained for reduced clearances.
3. Horizontal clearance shall be from edge of reinforced sidewalk bay or pole base to edge of proposed plant. Contractor shall at no time cut into reinforced sidewalk bays and pole bases. Sidewalk bays and pole bases provide loading support for the pole. Plant can be installed under reinforced sidewalk bays by tunneling at a minimum vertical clearance of 600 mm (2'-0"). Plant shall not be installed under pole bases.
- △ 4. If the minimum horizontal clearance for utilities installing plant close to THESL plant cannot be met due to existing field conditions, clearance can be reduced to 300mm (1'-0") with the Contractor/Customer providing the reasons for the reduced clearance. Approvals can be provided by Toronto Hydro Standards Department for reduced clearance.
- △ 5. Any proposed horizontal clearance less than 300 mm (1'-0") will require an ESA deviation with the following supporting documentation:
 - a) A letter stamped and signed by a Professional Engineer of Ontario, outlining:
 - That the Contractor/Customer is responsible for all costs associated with support and inspection, as well as any damages and associated costs;
 - The method of protection and/or support. Support is required if Toronto Hydro plant is undermined;
 - That this is a unique scenario that requires a deviation from typical construction standard, and identify that the deviation is also from the typical clearances set out by Toronto Hydro and the City of Toronto.
 - b) Drawing which shall include:
 - Stamp and signature of a Professional Engineer in the Province of Ontario;
 - Length of the plant being supported and/or protected;
 - Method of protection and/or support system in both plan and section views;
 - Maximum deflection of the plant with the support;
 - Deflection monitoring system placement if soil settlement will occur on site;
 - Backfilling procedures.
6. Contact the City of Toronto for minimum vertical clearance to water valve chamber.
7. For above grade clearance refer to:
 - 03-2300 Building and Permanent Structures
 - 03-2400 Poles and Private Fences
 - 04-4100 Pole Location Guidelines

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		UNDERGROUND CLEARANCES					
	Approved by:		Original issue: J.D. 2000-12-28	Scale: N.T.S.	Rev. 9	31-0100	2/2
	Drafted by: J.D.	Designed by: B.D.					



THE "MINIMUM DEPTH OF COVER" FOR THESE PLANT (CONDUITS AND CABLE CHAMBERS) SHALL BE AS FOLLOWS:

TYPE	MINIMUM DEPTH OF COVER	DESCRIPTION
CURBED ROADS	1000 (3'-4")	FOR AREAS UNDER THE ROAD, CURB, AND SIDEWALK, THE PORTION OF THE BOULEVARD WITHIN ONE METRE OF THE BACK OF CURB AND/OR SIDEWALK, AND THE ENTIRE RIGHT-OF-WAY WITHIN 30 METRES OF AN INTERSECTION, THE MINIMUM DEPTH OF COVER SHALL BE ONE METRE. △
UNCURBED ROADS	1300 (4'-3") BELOW THE CENTERLINE OF THE ROAD, OR 600 (2'-0") BELOW THE LOWEST POINT OF THE ADJACENT DITCH, WHICHEVER IS DEEPER.	FOR THE ENTIRE RIGHT-OF-WAY, FROM STREET-LINE TO STREET-LINE, ON UNCURBED ROADS. △
BOULEVARDS	800 (2'-8")	EXCEPT WHERE SPECIFIED ABOVE, THE MINIMUM DEPTH OF COVER ON ALL STREETS SHALL BE 800 MILLIMETRES. △

- NOTES:**
- 1) THE DEPTHS OF COVER ARE IN ACCORDANCE WITH THE CITY'S MUNICIPAL CONSENT REQUIREMENTS DOCUMENT.
 - 2) THE DEPTHS OF COVER APPLY TO ALL CONDUITS IRRESPECTIVE OF THE TYPE AND METHOD OF INSTALLATION.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2018-08-29

Drafted By: M.D. Designed By: B.D.

Original Issue:
J.D. 2010-10-21


Scale:
N.T.S.

Rev: **2**


31-0300

1/1


**UNDERGROUND CLEARANCES
MINIMUM DEPTH OF COVER
FOR TORONTO HYDRO STRUCTURES**




1 DUCT




**2W1H
2 DUCTS**




**3W1H
3 DUCTS**




**2W2H
4 DUCTS**




**3W2H
6 DUCTS**




**3W3H
9 DUCTS**



**3W4H
12 DUCTS**



**3W5H
15 DUCTS**



**4W6H
24 DUCTS**
SEE NOTE 2

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
J. D. 2017-08-14

Drafted By: B. D.
Designed By: J. D.

CONDUITS
CONCRETE ENCASED AND DIRECT BURIED DUCTS


Original Issue:
G. D. / C. P. 2002-07-11

Scale:
N. T. S.

Rev:
8


31-1120

1/2



REINFORCED DUCT BANK

SEE NOTE 3



DIRECT BURIED DUCTS


SEE NOTES 2, 9 and 10

NOTES:

- 1) REFER TO STD. 31-0300 FOR MIN. DEPTH OF COVER.
- 2) IN AN OPEN TRENCH CONSTRUCTION, ENCASE THE DUCTS IN CONCRETE IF:
 - DUCTS ARE CARRYING PRIMARY CABLES (750 V OR MORE),
 - DUCTS ARE UNDER ROADWAY OR DRIVEWAY,
 - DUCT HAVE 90 DEGREE BENDS,
 - THE NUMBER OF DUCTS ARE MORE THAN 8.
 IF NONE OF THE ABOVE CATEGORY APPLIES, THEN THE DUCTS SHALL BE DIRECT BURIED.
- 3) REINFORCED DUCT BANK SHALL BE USED ONLY IN POOR SOIL CONDITIONS OR WHERE THERE IS HIGH WATER TABLE.
- 4) CONCRETE SHALL BE A MIN. 20 MPa, WITH 10 mm (3/8") AGGREGATES.
- 5) REINFORCING SHALL CONFORM TO CSA STANDARD G30.18-09, Fy = 400 MPa.
- 6) ALL DUCTS SHALL BE 100 mm (4") IN DIAMETER UNLESS NOTED OTHERWISE.
- 7) HORIZONTAL AND VERTICAL SEPARATION BETWEEN DUCTS IS CONTROLLED DURING CONSTRUCTION BY PLASTIC DUCT SPACERS.
- 8) EXCAVATION SHALL BE BACKFILLED TO GRADE AS PER SPECIFICATION #CV-CON-01 CLAUSE 5.1.17 AND/OR TORONTO'S LATEST BACKFILLING REQUIREMENT.
- 9) MAX. NUMBER OF DIRECT BURIED DUCTS SHALL BE 8. DUCTS MAY BE PLACED IN AN IRREGULAR FORMATION IN A MAX. OF TWO ROWS.
- 10) RED DUCT SHALL BE USED IN ALL NEW AND REBUILD UNDERGROUND DIRECT BURIED INSTALLATIONS. THIS INCLUDES ELECTRICAL CABLES AND COMMUNICATION CABLES. IF REQUIRED, 50 mm (2") DUCT CAN BE USED FOR COMMUNICATION CABLES.


DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		CONDUITS				
Approved By: J.D. 2017-08-14		CONCRETE ENCASED AND DIRECT BURIED DUCTS				
Drafted By: B.D.	Designed By: J.D.	Original Issue: G.D. /C.P. 2002-07-11	Scale: N.T.S.	Rev: 8	31-1120	2/2






DETAIL "A" ⚠

NOTE: THIS ALSO APPLIES TO DIRECT BURIED DUCTS AND POLYPIPES



DETAIL "B" ⚠
REDUCED DEPTH OF COVER



SECTION A-A ⚠

NOTES: ⚠

- 1) IF UNDER SPECIFIC CIRCUMSTANCES MINIMUM DEPTH OF COVER REQUIREMENT CANNOT BE MET, REDUCED COVER MAY BE USED WITH CITY'S APPROVAL. THE REDUCED COVER SHALL NOT BE LESS THAN 450 mm (1'-6").
- 2) IF MINIMUM DEPTH OF COVER IS REDUCED, A 10 mm STEEL PLATE AND WARNING TAPE HAS TO BE PROVIDED AS SHOWN IN DETAIL "B".

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CONDUITS
DEPTH OF CONDUITS



Approved By:
B.D. 2018-08-31

Drafted By:
B.D.

Designed By:
B.D.


Original Issue:
G.D. / L.G. 2000-12-19

Scale:
N.T.S.

Rev:
6


31-1150

1/1




SECTION VIEW 'A'

DUCTS FROM THESL STRUCTURES TO CUSTOMER'S BUILDING/VAULT



SECTION VIEW 'B'

DUCTS FROM THESL STRUCTURES TO CUSTOMER'S BUILDING/VAULT



SECTION VIEW 'C'

DUCTS FROM THESL POLES TO CUSTOMER'S BUILDING/VAULT

NOTES:

- 1) SEALANT SHALL BE APPLIED TO:
 - DUCTS EXITING THESL STRUCTURES (POLES, CABLE CHAMBERS, PADMOUNTS, SPLICE VAULTS, TAP/SPLICE BOXES AND VAULTS) WHEN FEEDING INTO CUSTOMER'S BUILDING/VAULTS AND ALSO DUCTS AT CUSTOMER'S BUILDING/VAULTS ENTRANCE POINT;
 - LOCATIONS WHERE EXISTING SEALANT (STOCK CODES 8940011, 9656790 OR 9656791) IS NOT ADEQUATE.
- 2) DRILL 4 DRAINAGE HOLES IN THE BOTTOM OF EACH DUCT. 13 mm (1/2") DIA. AT 50 mm (2") CENTRES. FILL TO TOP OF DUCTS WITH 19 mm (3/4") CLEAR STONE. TOP OFF WITH A LAYER OF 25 mm (1") STYROFOAM, AND A FINAL LAYER OF CONCRETE.
- 3) REFER TO STD. 31-0300 FOR MIN. DEPTH OF COVER.
- 4) CUSTOMER IS RESPONSIBLE TO CONSTRUCT SOAKAWAY PIT ON CUSTOMER PROPERTY AS INDICATED ABOVE.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
2021/10/21

Drafted By:
J.D.

Designed By:
B.D.

Original Issue:
G.D./C.P. 2002-11-25


Scale:
N.T.S.

Rev:
5

31-1230

1/1

**CONDUITS
SUPPLYING CUSTOMER'S BUILDING**



**CONCRETE ENCASED DUCTS
TIMBER BOX DETAIL**

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

DUCT OR CABLE

SUPPORT IN PLACE SYSTEM



Approved By:

Drafted By:
B.D.

Designed By:
J.D.


Original Issue:
G.D./C.P. 2002-11-25

Scale:
N.T.S.

Rev: **3**

31-1350

1/4




**CONCRETE ENCASED DUCTS
SUPPORT FROM BELOW**


DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**DUCT OR CABLE
SUPPORT IN PLACE SYSTEM**

	Approved By:		Original Issue:		Scale:	Rev:	3	31-1350	2/4
	Drafted By: B.D.	Designed By: J.D.	G.D. /C.P. 2002-11-25		N.T.S.				



DIRECT BURIED DUCT OR CABLE



SECTION 'A-A'

MULTIPLE CABLES OR DUCTS

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

DUCT OR CABLE

SUPPORT IN PLACE SYSTEM



Approved By:

Drafted By:
B.D.

Designed By:
J.D.

Original Issue:
G.D./C.P. 2002-11-25

Scale:
N.T.S.

Rev: **3**

31-1350

3/4

NOTES: 

- 1) THIS DRAWING IS TO BE USED ONLY AS A GUIDELINE AS THE SUPPORT STRUCTURE ELEMENTS WILL BE SITE SPECIFIC.
- 2) TEMPORARY SUPPORT IS REQUIRED WHENEVER THE UNDERGROUND CONDUIT IS UNDERMINED FOR MORE THAN 1200 mm (3'-11") IN LENGTH. ALL SUCH SUPPORTS SHALL MEET REQUIREMENTS OF NOTE #2.
- 3) THE CONTRACTOR/CONSULTANT SHALL PROVIDE A DETAILED DRAWING FOR THE SUPPORT SYSTEM SIGNED AND SEALED BY A PROFESSIONAL CIVIL ENGINEER OF ONTARIO TO SUIT SITE CONDITIONS. ENGINEER SHALL ACCOUNT FOR CABLE PULLING TENSION, LIVE LOADS, WIND LOADS, AND MAINTANENCE LOADS IN THEIR CALCULATIONS.
- 4) WHEN SUPPORTED FROM ABOVE, DIRECT BURIED DUCTS AND DIRECT BURIED CABLE, SPACING BETWEEN SUPPORTS SHALL NOT EXCEED 0.6 m (2'-0").
- 5) FOR CONCRETE ENCASED AND DIRECT BURIED DUCTS, VERTICAL OR HORIZONTAL DISPLACEMENT SHALL NOT EXCEED 19 mm (3/4") OR 10 mm (3/8"), RESPECTIVELY. STRUCTURAL DAMAGE OR DISPLACEMENT OUTSIDE OF THIS RANGE SHALL BE REPORTED TO TORONTO HYDRO.
- 6) FOR CONCRETE ENCASED AND DIRECT BURIED DUCTS, MONITORING OF SUPPORT STRUCTURE WITH RESPECT TO HORIZONTAL, VERTICAL, AND VIBRATIONAL MOVEMENTS SHALL BE PROVIDED.
- 7) TEMPORARY SUPPORT WILL REMAIN IN-PLACE UNTIL THE BACK FILL MATERIAL UNDER THE STRUCTURE HAS BEEN COMPACTED ADEQUATELY TO RESTORE SUPPORT. BACKFILL ON TOP TO BE AS PER CV-CDN-01.
- 8) ALTERNATIVE METHODS OF SUPPORT SYSTEM CAN BE CHOSEN BUT WILL REQUIRE TORONTO HYDRO TO REVIEW AND APPROVE.
- 9) TIMBER BOX TO BE PAINTED RED AND MARKED WITH SAFETY "DANGER" SIGN.
- 10) DAMAGED DIRECT BURIED DUCTS OR CONCRETE ENCASED DUCTS WILL REQUIRE TO BE REBUILT PRIOR TO SUPPORT IN PLACE INSTALLATION.
- 11) CONTRACTOR IS RESPONSIBLE TO MEET ALL REQUIREMENTS WITH CONSIDERATION TO SUPPORTING OR WORKING CLOSE TO LIVE ENERGIZED CABLES.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

DUCT OR CABLE
SUPPORT IN PLACE SYSTEM



Approved By:

Drafted By:
B. D.

Designed By:
J. D.


Original Issue:
G. D. / C. P. 2002-11-25

Scale:
N. T. S.

Rev: **3**

31-1350

4/4



**DUCT IDENTIFICATION IN GARAGE FLOOR,
CEILING OR INTERIOR WALL**



**DUCT IDENTIFICATION IN GROUND LEVEL FLOOR
UNDER CARPET OR FLOORING**

NOTES: ⚠

- 1) CABLE MARKER TO BE INSTALLED FLUSH WITH SURFACE OF DUCT STRUCTURE.
- 2) PAINT STRIP TO BE 600 mm (2'-0") WIDE OR MAXIMUM WIDTH OF DUCT STRUCTURE.
- 3) FLUORESCENT PAINT TO BE RED EXTERIOR ACRYLIC LATEX.
- 4) LETTERING TO BE BLACK EXTERIOR LATEX PAINT.
- 5) PERMANENT IDENTIFICATION MUST BE COMPLETED BEFORE THE SERVICE IS ENERGIZED.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CONDUITS
IDENTIFICATION OF HYDRO DUCTS IN BUILDING COMPLEXES**



Approved By:
J.D. 2012-11-09

Drafted By: D.L.
Designed By: J.D.

Original Issue:
G.D./C.P. 2004-03-31


Scale:
N.T.S.

Rev:


1

31-1360


1/1



DUCT BANK
FRONT VIEW



SECTION 'A-A'



INSTALLATION IN DRY DUCT

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

DUCT SEALANT INSTALLATION



Approved By: 2021/10/21

Drafted By: J.D.

Designed By: B.D.



Original Issue: J.D. 2015-11-23

Scale: N.T.S.


Rev: 2

31-1400


1/3



INSTALLATION IN WET OR LEAKING DUCT



ADDING ADDITIONAL CABLES



DETAIL 'A'

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		DUCT SEALANT INSTALLATION					
Approved By: 2021/10/21							
	Drafted By: J.D.	Designed By: B.D.	Original Issue: J.D. 2015-11-23	Scale: N.T.S.	Rev: 2	31-1400	2/3

BILL OF MATERIALS FOR 31-1400			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
* 1	DUCT SEALANT KIT	9665194	1
+ 2	SEALANT	9665195	1
+ 3	CAULKING GUN	2730104	1

+ AS REQUIRED

* DUCT SEALANT KIT INCLUDES:

- NOFIRNO FILLER SLEEVES

- BLACK RISE INSERT SLEEVES

- AQUASTOP

NOTES:

1) SEALANT SHALL BE APPLIED TO:



- DUCTS EXITING THESE STRUCTURES (POLES, CABLE CHAMBERS, PADMOUNTS, SPLICE VAULTS, TAP/SPLICE BOXES AND VAULTS) WHEN FEEDING INTO CUSTOMER'S BUILDING/VAULTS AND ALSO DUCTS AT CUSTOMER'S BUILDING/VAULTS ENTRANCE POINT;

- LOCATIONS WHERE EXISTING SEALANT (STOCK CODES 8940011, 9656790 OR 9656791) IS NOT ADEQUATE.

2) INSTALLATION IN DRY DUCT (AS PER SECTION 'A-A'):

A) CLEAN THE DUCT AND CABLE THOROUGHLY USING A CLOTH TO REMOVE ALL DEBRIS AND DIRT FROM INSIDE THE DUCT. DO NOT USE HAND SANITIZER CLOTHS OR CLOTHS MIXED WITH SOAPY MIXTURE.

B) PLACE BLACK RISE INSERT SLEEVES AROUND EACH CABLE.

C) FILL THE REMAINDER OF THE SPACE IN DUCT WITH RED NOFIRNO FILLER SLEEVES 22/15 (22 mm ($\frac{9}{10}$ ") OUTER DIAMETER AND 15 mm ($\frac{3}{8}$ ") INNER DIAMETER).

D) ADJUST THE SLEEVES SO THAT THEY ARE ALIGNED AND RECESSED, BY USING NEEDLE NOSE PLIERS.

E) OVERFILL THE DUCT WITH NOFIRNO SEALANT.

F) USING A WET CLOTH, COMPRESS AND SMOOTHEN THE NOFIRNO SEALANT FOR A SMOOTH SURFACE.

3) INSTALLATION IN WET OR LEAKING DUCTS (AS PER SECTION 'B-B'):

A) FOLLOW PROCEDURES AS PER 2A, 2B AND 2C.

B) INSERT THE AQUASTOP INTO THE DUCT AGAINST THE NOFIRNO FILLER SLEEVES.

C) TIGHTLY COMPRESS THE AQUASTOP AGAINST THE FILLER SLEEVES BY HAND OR BY USING A WOOD PIECE OR ANY OBJECT WITH A FLAT SURFACE.

D) ENSURE THE EDGES ARE PROPERLY SEALED BY SMEARING THE AQUASTOP RUBBER ALONG THE EDGES OF THE DUCT WALL. ENSURE THAT THERE IS AT LEAST 19 mm ($\frac{3}{4}$ ") OF SPACING BETWEEN THE FINAL LAYER OF AQUASTOP STRIP AND DUCT EDGE.

E) INSPECT THE DUCT TO ENSURE THAT THE LEAKAGE HAS STOPPED. IN ORDER TO EXPEDITE DRYING TIME, USE A DRYER. DO NOT USE A HEAT GUN, AS PROLONGED USE WILL DAMAGE CABLE.

F) APPLY THE NOFIRNO SEALANT OVER THE AQUASTOP UNTIL THE DUCT OVERFLOWS.

G) USING A WET CLOTH, COMPRESS AND SMOOTHEN THE NOFIRNO SEALANT.

4) ADDING ADDITIONAL CABLES TO DRY DUCT CONTAINING NOFIRNO SEALANT (AS PER DETAIL 'A'):

A) USING A KNIFE, PENETRATE THE NOFIRNO SEALANT LAYER (AND AQUASTOP LAYER, IF APPLICABLE) AND BEGIN TO CUT SEALANT WIDE ENOUGH TO ACCOMMODATE THE OUTER DIAMETER OF THE CABLE TO BE PULLED INTO THE DUCT. A TAPERING MOTION SHALL BE USED TO ENSURE APPROPRIATE MASS IS AVAILABLE FOR RE-SEAL.

B) REMOVE THE APPROPRIATE AMOUNT OF NOFIRNO FILLER SLEEVES, IN ORDER TO ACCOMMODATE THE OUTER DIAMETER OF THE CABLE TO BE PULLED INTO THE DUCT.

C) PULL THE DESIRED CABLE THROUGH THE DUCT AND ADD A BLACK RISE INSERT SLEEVE AROUND THE CABLE.

D) PUSH THE RISE INSERT SLEEVES INTO THE DUCT AT A DEPTH OF 19 mm ($\frac{3}{4}$ ") FROM THE DUCT OPENING.

E) FOLLOW PROCEDURES AS PER 2D AND 2E.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
2021/10/21

DUCT SEALANT INSTALLATION

Drafted By:
U. K.

Designed By:
B. D.

Original Issue:
J. D. 2015-11-23


Scale:
N. T. S.

Rev:


2

31-1400

3/3



CONNECTION INTO EXISTING WALL



ELEVATION VIEW

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2019-03-22

Drafted By:
B.D.

Designed By:
B.D.

Original Issue:
B.D. 2019-03-22

Scale:
N.T.S.

Rev: 0

31-1600

1/2

**CONDUITS
NEW DUCT BANK RECESS
INSTALLATION IN EXISTING STRUCTURES**

NOTES:

- 1) DRILL 15M DOWEL BARS INTO EXISTING CONCRETE WALL FOR A LENGTH OF AT LEAST 200 mm (8"). USE HILTI HY-200 CHEMICAL ADHESIVE ANCHORS ACCORDING TO THE MANUFACTURERS INSTRUCTIONS.
- 2) ALL REINFORCEMENT BARS SHALL CONFORM TO LATEST CSA STANDARD G30.18, Fy=400 MPa.
- 3) WITHIN 700 MM OF EXTERIOR WALL FACE, CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 35 MPa AND EXPOSURE CLASS OF C-1 AS DEFINED IN CSA A23.1.
- 4) FOR CABLE CHAMBERS, IF CABLE PULLING LOOPS ARE REQUIRED, INSTALL IN ACCORDANCE TO TORONTO HYDRO STANDARD 31-8220. CABLE PULLING LOOP SHALL BE IN-LINE WITH AND ON OPPOSITE WALLS OF EACH DUCT FACE (TYPICAL 300 mm (1'-0") FROM FINISHED FLOOR).
- 5) DUCT BANK RECESS INSTALLATION SHALL APPLY TO DUCT CONFIGURATIONS GREATER THAN 6 DUCTS. NUMBER OF DUCTS WITHIN RECESS SHALL NOT EXCEED 24. DUCT CONFIGURATIONS SHALL BE IN ACCORDANCE WITH STD. 31-1120.
- 6) FOR DUCT BANK RECESS INSTALLED IN EXISTING STRUCTURES, CLEARANCES SHALL BE AS FOLLOWS:
 - MIN. 400 mm (1'-4") FROM CEILING;
 - MIN. 400 mm (1'-4") FROM ADJACENT WALLS;
 - MIN. 400 mm (1'-4") FROM OTHER DUCT BANKS.
 - MIN. 400 mm (1'-4") FROM FLOOR OR, IF APPLICABLE, MIN. 100 mm (4") ABOVE BACKWATER VALVE.
- 7) TO PREVENT DAMAGE TO REINFORCEMENT BARS ADJACENT TO RECESS, SAW OVERRUN SHALL BE AVOIDED DURING RECESS INSTALLATION.
- 8) INSTALLATION SHALL CONFORM TO THE LATEST EDITION OF TORONTO HYDRO TECHNICAL SPECIFICATION FOR CIVIL CONSTRUCTION WORK CV-CON-01.
- 9) THE CONTRACTOR SHALL ENSURE THAT THE WALL IS STRUCTURALLY SOUND PRIOR TO COMMENCING WORK. MINIMUM WALL THICKNESS SHALL BE 200 mm (8"). OTHERWISE CORE DRILLING SHALL BE USED FOR STRUCTURES HAVING WALL THICKNESS LESS THAN 200 mm (8"). NO RECESS SHALL BE INSTALLED IN A SUBMERSIBLE TRANSFORMER VAULT.
- 10) DUCT BANK RECESS SHALL BE PERFORMED BY AN APPROVED TORONTO HYDRO CONTRACTOR TO ENSURE THAT CONSTRUCTION COMPLIES WITH TORONTO HYDRO CIVIL SPECIFICATIONS, STANDARDS AND ALL RELEVANT ACCEPTABLE PRACTICES AND METHODS APPROVED BY TORONTO HYDRO.
- 11) THE CONTRACTOR SHALL PROVIDE TEMPORARY PROTECTION TO ALL CABLES LOCATED INSIDE THE STRUCTURE, AND WILL CLEAN, REMOVE AND DISPOSE OF ALL DEBRIS RESULTING FROM THE CONSTRUCTION.
- 12) THIS INSTALLATION SHALL NOT APPLY TO STRUCTURES CONSTRUCTED WITH CONCRETE BLOCKS/BRICKS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2019-03-22

Drafted By:
B.D.

Designed By:
B.D.

Original Issue:
B.D. 2019-03-22


Scale:
N.T.S.

Rev:
0

31-1600

2/2

CONDUITS
NEW DUCT BANK RECESS
INSTALLATION IN EXISTING STRUCTURES



PLAN VIEW

NOTES:

- 1) ROOF SLAB AND WALLS SHALL BE DESIGNED IN ACCORDANCE WITH CANADIAN HIGHWAY BRIDGE DESIGN CODE CAN/CSA-S6-06, CL-625-ONT LIVE LOADING.
- 2) ALL CONCRETE SHALL HAVE A MIN. 28-DAY COMPRESSIVE STRENGTH OF 35 MPa. CONCRETE MIX AND PLACEMENT SHALL CONFORM TO LATEST CSA-A23.1. ALL TESTING SHALL CONFORM TO LATEST CSA-A23.2.
- 3) ALL REINFORCEMENT BARS SHALL CONFORM TO LATEST CSA STANDARD G30.18, Fy=400 MPa.
- 4) MIN. DISTANCE FROM CABLE CHAMBER ACCESS CHIMNEY (NECK) OPENING SHALL BE 450 (1'-6"). FOR 1000 kcmil XLPE CABLES, REFER TO STD. 31-2170 FOR MIN. DISTANCE FROM THE NECK.
- 5) THE EXTERIOR SURFACE OF THE ROOF AND NECK SHALL BE WATERPROOFED WITH A BITUMEN MEMBRANE.
- 6) PARGING MIX ON ALL BRICK WORK SHALL BE ONE PART NON-SHRINK CEMENT AND THREE PARTS SAND AND APPLIED 15 mm THICK.
- 7) CABLE PULLING LOOP SHALL BE IN-LINE WITH AND ON OPPOSITE WALL OF EACH DUCT FACE (TYPICAL 300 mm (1'-0") FROM FINISH FLOOR).
- 8) SUMP HOLE REMOVABLE TYPE GRATING, SHALL BE GALVANIZED AS PER LATEST CSA-G-164.
- 9) EXACT LOCATION OF FLOOR DRAIN OR SUMP HOLE SHALL BE DETERMINED AS PER CONSTRUCTION DRAWING.
- 10) LOCATION AND CONFIGURATION OF DUCT BANK SHALL BE AS DETAILED ON PROJECT CONSTRUCTION DRAWING.
- 11) CHAMBER SIZES SHALL BE AS SHOWN IN TABLE.
- 12) STRUCTURAL DESIGN OF PRECAST CHAMBER IS THE RESPONSIBILITY OF THE CONTRACTOR. DRAWINGS SHALL BE STAMPED AND SIGNED BY CONTRACTOR'S PROFESSIONAL ENGINEER.
- 13) CONTRACTOR OR MANUFACTURER SHALL SUBMIT SHOP DRAWINGS FOR REVIEW AND APPROVAL BY TORONTO HYDRO PRIOR TO FABRICATION.
- 14) MIN. WALL THICKNESS SHALL BE 200 mm (8").
- 15) IF CHAMBER WALLS ARE BUILT IN SECTIONS, SEAL BETWEEN SECTIONS SHALL BE INSTALLED TO PREVENT WATER FROM ENTERING THE CABLE CHAMBER.
- 16) ALL DUCT HOLES SHALL BE PLUGGED WITH DUCT PLUGS.
- 17) 4 GROUND RODS PROVISION SHALL BE PLACED IN FOUR CORNERS OF THE CABLE CHAMBER.
- 18) DELIVERY IS MADE BY CRANE-EQUIPPED TRUCKS, EXCAVATION SHALL BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK. MIN. OVERHEAD CLEARANCE OF 5500 mm (18'-0") IS REQUIRED.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CABLE CHAMBERS
PRECAST CHAMBER**



Approved By:
J. D. 2014-10-08

Drafted By: Y. A.
Designed By: J. D.


Original Issue:
G. D. / L. G. 2000-12-30

Scale:
N. T. S.

Rev:
9

31-2160

1/2



SECTION "A-A"

CHAMBER SIZES		
TYPE #	WIDTH	LENGTH
1	2000 (6'-8")	2500 (8'-4")
2	2000 (6'-8")	3000 (10'-0")
3	2500 (8'-4")	3000 (10'-0")
4	2500 (8'-4")	3500 (11'-6")
5	2500 (8'-4")	4000 (13'-4")
6	3000 (10'-0")	3000 (10'-0")
7	3000 (10'-0")	3500 (11'-8")
8	3000 (10'-0")	4000 (13'-4")
9	3500 (11'-8")	4000 (13'-4")

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction


**CABLE CHAMBERS
PRECAST CHAMBER**

Approved By:
J. D. 2014-10-08
Drafted By:
Y. A.


Designed By:
J. D.
Original Issue:
G. D. /L. G. 2000-12-30

Scale:
N. T. S.
Rev: **9**
31-2160
2/2






PLAN VIEW




SECTION 'A-A'




SECTION 'B-B'


DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		VAULTS				
		SPLICE VAULT 'B' - 3 PIECE PRECAST				
		1930 mm (6'-4") x 3050 mm (10'-0") x 1370 (4'-6") mm DEEP				
	Approved By: B.D. 2018-08-28	Original Issue: G.D./C.P. 2003-05-30		Scale: N.T.S.	Rev: 8	31-2240 1/4
	Drafted By: M.D.	Designed By: B.D.				



TYPICAL SPLICE RACKING



**DETAIL 'A'
WALL AND FLOOR REINFORCEMENT**



ISOMETRIC

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2018-08-28

Drafted By:
M.D.

Designed By:
B.D.

Original Issue:
G.D./C.P. 2003-05-30

VAULTS

SPLICE VAULT 'B' - 3 PIECE PRECAST
1930 mm (6'-4") x 3050 mm (10'-0") x 1370 (4'-6") mm DEEP


Scale:
N.T.S.

Rev:

8

31-2240

2/4



CABLE SUPPORT

NOTES:

MATERIAL:

- 1) CONCRETE SHALL HAVE A MIN. 28-DAY COMPRESSIVE STRENGTH OF 35 MPa. CONCRETE PRODUCTION AND PLACEMENT SHALL CONFORM TO LATEST CSA-A23.1. ALL TESTING SHALL CONFORM TO LATEST CSA-A23.2.
- 2) MANUFACTURER SHALL ADD DATE OF MANUFACTURE STAMP ON ALL PRECAST UNITS.
- 3) EXPOSURE CLASSIFICATION TO FREEZING AND THAWING IN A SATURATED CONDITION BUT WITH NO CHLORIDES SHALL BE F-1. ALL REINFORCING TO CONFORM TO LATEST CSA STANDARD G30.18, $F_y = 400 \text{ MPa}$.
- 4) CONCRETE COVER ON PRECAST UNIT SHALL BE 50 mm (2").
- 5) ALL EXPOSED EDGES SHALL HAVE 25 mm (1") CHAMFER.
- 6) LIFTING HOLES CAN BE INSTALLED IN FOUNDATION WALLS FOR MANUFACTURER'S LIFTING PREFERENCE.
- 7) 4-LIFTING ANCHORS FOR LIFTING PURPOSES BY OTHERS SHALL BE PROVIDED ON THE INSIDE OF ALL FOUNDATION WALLS. LIFTING ANCHORS SHALL BE GALVANIZED. LIFTING ANCHORS SHALL BE CAPABLE OF LIFTING THE PRECAST UNITS AND THIS SHALL BE CERTIFIED BY MANUFACTURER PRIOR TO DELIVERY.

INSTALLATION:

- 8) PLACE 150 mm (6") GRANULAR "A" BEDDING ON UNDISTURBED SOIL CAPABLE OF SUSTAINING 75 KPa AND COMPACT TO 95% STANDARD PROCTOR DENSITY.
- Ⓜ 9) EXCAVATION SHALL BE BACKFILLED TO FINISHED GRADE AS PER TORONTO HYDRO CIVIL SPECIFICATION CV-CON-01 AND/OR CITY OF TORONTO'S LATEST BACKFILLING REQUIREMENT.
- Ⓜ 10) TORONTO HYDRO INSPECTOR SHALL BE PRESENT DURING THE INSTALLATION, 24-HOUR NOTICE IS REQUIRED PRIOR TO STARTING THE INSTALLATION.
- Ⓜ 11) DRAIN CONNECTION SHALL BE AS PER STANDARD 31-7100.
- Ⓜ 12) UNUSED CABLE ENTRY DUCTS SHALL BE PLUGGED WITH DUCT PLUGS AND PARGED PRIOR TO BACKFILLING.
- Ⓜ 13) CONTRACTOR TO PLUG ALL HOLES (LIFTING AND GROUNDING) AND PARGED PRIOR TO BACKFILLING.
- Ⓜ 14) PRECAST UNITS ARE DELIVERED BY CRANE-EQUIPPED TRUCKS. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK. MIN. OVERHEAD CLEARANCE OF 5500 mm (18'-0") IS REQUIRED. CONTRACTOR SHALL ASSIST SUPPLIER IN LOWERING THE PRECAST UNITS INTO EXCAVATION.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2018-08-28

Drafted By:
M.D.

Designed By:
B.D.

Original Issue:
G.D./C.P. 2003-05-30

VAULTS

SPLICE VAULT 'B' - 3 PIECE PRECAST
1930 mm (6'-4") x 3050 mm (10'-0") x 1370 (4'-6") mm DEEP

Scale:
N.T.S.

Rev:

8

31-2240

3/4

BILL OF MATERIALS FOR 31-2240

ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
1	PRECAST CONCRETE 3 PIECE SUBMERSIBLE SPLICE VAULT C/W FRAME, CHECKER PLATES AND SUPPORT BEAMS 1930 X 3050 X 1370 mm DEEP	3540040	1
2	CHANNEL STEEL GALV. 41 mm x 41 mm x 3000 mm (1 ⁵ / ₈ " x 1 ⁵ / ₈ " x 10')	3520220	4
3	ANCHOR STUD BOLT WEDGE 3/8" X 3"	2500057	24
4	WASHER BELLVILLE 1/2"	2530100	24
5	CLAMP CABLE 1 1/4" HOLE THERMOPLASTIC	9663121	24
6	NUT PENTA 1/2"-13 UNC ZINC ALLOY	2520095	24
ASSOCIATED STANDARDS			
7	FRAME, BEAMS AND COVER	STD. 31-8310	1
8	GROUNDING	STD. 18-5400	1
9	VAULT LOCATION NUMBER	STD. 21-3100	1
10	DRAINING STRUCTURES	STD. 31-7100	1



DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2018-08-28

Drafted By:
M.D.

Designed By:
B.D.

Original Issue:
G.D./C.P. 2003-05-30

Scale:
N.T.S.


Rev: 8

31-2240


4/4

VAULTS

**SPLICE VAULT 'B' - 3 PIECE PRECAST
1930 mm (6'-4") x 3050 mm (10'-0") x 1370 (4'-6") mm DEEP**




BOX PLAN VIEW ⚠




LID PLAN VIEW ⚠
COMPOSITE POLYMER LID



**LOGO PUCK
DETAIL**



ISOMETRIC VIEW



BOX SIDE VIEW - SHORT SIDEWALL

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

SPLICE/TAP BOX ⚠

TYPE 'C' - 914 mm (3'-0") x 1514 mm (5'-0") - FOR PRIMARY CABLES



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
B. D. 2022-01-31


Scale:
N. T. S.

Rev:


1

31-3170

1/3



BOX SIDE VIEW 
LONG SIDEWALL



BOX SIDE VIEW
INSTALLATION DETAIL



NON-SLIP LID SURFACE



LID LIFTING HOOK
ID #9666054




LIFTING PIN ACCESS COVER




BOLT DOWN KIT

LID DETAIL



STEP BRACKET



HOOK BRACKET

CABLE BRACKETS

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
B. D. 2022-01-31

SPLICE/TAP BOX

TYPE 'C' - 914 mm (3'-0") x 1514 mm (5'-0") - FOR PRIMARY CABLES

Scale:
N. T. S.

Rev:

1

31-3170

2/3



BOM LEGEND	
A	SPLICE/TAP BOX TYPE 'C'
B	REPLACEMENT ACCESSORIES



BILL OF MATERIALS FOR 31-3170				
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY	
			A	B
1	1 - 1060x1657x1219 mm HDPE BOX 1 - COMPOSITE POLYMER LID 4 - 8 mm PENTA HEAD BOLTS 4 - WASHERS 2 - 4" STEP BRACKETS (WITH 2 WEDGES) 2 - 4" HOOK BRACKETS		1	-
2	LID KIT CW 1-915x1514 LID, 2-PENTA BOLTS, 2-RETAINERS, 2-WASHERS		-	1
3	BOLT DOWN KIT CW - PENTA LAG W/RETAINERS AND WASHERS (2/PACKAGE)	100001689	-	1
4	4" STEP BRACKETS	100001690	-	1
5	4" HOOK BRACKETS	100001691	-	1

*
*
*
*

* WHEN REQUIRED


NOTES:

- FOR LEGACY LID REPLACEMENTS ONLY, REFER TO FOLLOWING STOCK CODES:
 - COVER GREEN HDPE WITH LOCKING ASSEMBLY: ID# 9663405
 - PENTA HEAD BOLT LOCKING ASSEMBLY: ID# 9663408
- AS SHOWN, BOX COMES WITH PRE DRILLED 125 mm (5") HOLES ON EACH SIDEWALL. IF REQUIRED, A MAX. OF 2 ADDITIONAL HOLES CAN BE DRILLED IN ALL SIDEWALLS BY USING A STANDARD HOLE SAW OR A DRILL BIT. AVOID DRILLING HOLES OR CUTTING AT THE FOLLOWING LOCATIONS:
 - THE BOX'S CENTRAL SPINE (LOCATED IN THE SHORT SIDEWALLS),
 - TOP 300 mm (1'-0") OF THE BOX.
- BOX SHALL BE INSTALLED IN GRASSY OR PAVED BOULEVARDS. FOR INSTALLATION IN SIDEWALKS, APPROVAL IS REQUIRED FROM THE CITY OF TORONTO. FOR OPERATIONAL REASONS, BOX SHALL NOT BE INSTALLED IN ROADS, DRIVEWAYS OR AREAS WITH CONSISTENT VEHICULAR TRAFFIC.
- TO REMOVE A FROZEN LID, MANUFACTURER RECOMMENDS HITTING AROUND PENTA BOLT LOCATIONS WITH SLEDGE HAMMER TO LOOSEN BOLTS.
- LIFTING HOOK SHALL BE USED TO REMOVE LID (ITEM ID# 9666054).


INSTALLATION NOTES:

- EXCAVATE 150 mm (6") LARGER THAN THE WIDTH AND LENGTH OF THE BOX.
- EXCAVATE 300 mm (1'-0") DEEPER THAN THE OVERALL DEPTH OF THE BOX. TAMP THE BOTTOM OF THE EXCAVATION TO COMPRESS AND FLATTEN ANY LOOSE SOIL.
- PLACE 300 mm (1' -0") OF 19 mm (3/4") CRUSHED STONE BEDDING OVER THE ENTIRE FLOOR OF THE EXCAVATION. THE CRUSHED STONE SHALL BE FREE OF SOIL AND OTHER ORGANIC MATTER. THIS PREVENTS SETTLEMENT, AIDS IN DRAINAGE, AND PROVIDES A SOLID BEDDING. AS AN ALTERNATIVE, A DRY MIX OF CEMENT AND CRUSHED ROCK IN A 1:10 RATIO MAY BE USED TO FORM A HIGHER STRENGTH BEDDING.
- PLACE THE BOX IN THE EXCAVATION AND LEVEL SO THAT THE BOX IS FLUSH WITH FINISHED GRADE BY ADDING/ADJUSTING THE BEDDING.
- COMPLETE EXCAVATION SHALL BE BACKFILLED WITH UNSHRINKABLE FILL TO WITHIN 100 mm (4") FROM FINISHED GRADE. CARE SHALL BE TAKEN SO NOT TO CAUSE EXCESSIVE DAMAGE TO THE BOX'S CELLULAR RIBS DURING THE BACKFILLING PROCESS.
- BACKFILL THE REMAINING 100 mm (4") TO FINISHED GRADE AS PER SPECIFICATION #CV-CON-01 AND/OR CITY OF TORONTO'S LATEST BACKFILLING REQUIREMENT.

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		SPLICE/TAP BOX				
Approved By:		TYPE 'C' - 914 mm (3'-0") x 1514 mm (5'-0") - FOR PRIMARY CABLES				
	Drafted By:	Designed By:	Original Issue:	Scale:	Rev:	
	J. D.	B. D.	B. D. 2022-01-31	N. T. S.	1	31-3170 3/3



**PAD-MOUNT AND FOOTING
PLAN VIEW**



SECTION VIEW

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
C. P. / G. D. 2002-07-11

Scale:
N. T. S.


Rev: 16

31-4030


1/3

PAD-MOUNTS
THREE PHASE PRECAST PAD-MOUNT
1830 mm (6'-0") x 1830 mm (6'-0")







FOOTING PLAN VIEW



ISOMETRIC VIEW



**THREE PHASE TRANSFORMER LID
PLAN VIEW**



**METERING LID
PLAN VIEW**

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
C. P. / G. D. 2002-07-11

Scale:
N. T. S.

Rev:

16

31-4030

2/3

PAD-MOUNTS
THREE PHASE PRECAST PAD-MOUNT
1830 mm (6'-0") x 1830 mm (6'-0")



BILL OF MATERIALS FOR 31-4030

ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
1	FOUNDATION PAD 1830 mm x 1830 mm x 1220 mm DEEP	3540014	1
2	STRIP FOOTING (FLOOR) 1980 mm x 1980 mm x 200 mm, 300 mm WIDE	9656479	1
3	LID (COVER) 1830 mm x 1830 mm x 150 mm DEEP - FOR THREE PHASE TRANSFORMER PAD	3540022	1
4	LID (COVER) 1830 mm X 1830 mm X 150 mm - FOR THREE PHASE METERING PAD	9662541	1
ASSOCIATED STANDARDS			
5	GUARD POSTS (BOLLARDS)	STD. 31-4080	1
6	CLEARANCE ZONE	STD. 31-4100	1
7	GROUNDING REQUIREMENTS	STD. 18-5500	1

NOTES:

MATERIALS: 

- 1) CONCRETE SHALL HAVE A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 35 MPa. CONCRETE PRODUCTION AND PLACEMENT SHALL CONFORM TO LATEST EDITION OF CSA-A23.1. ALL TESTING SHALL CONFORM TO LATEST CSA-A23.2.
- 2) MANUFACTURER SHALL ADD DATE OF MANUFACTURE STAMP ON ALL PRECAST UNITS.
- 3) CONCRETE EXPOSURE CLASSIFICATION SHALL BE C-1.
- 4) ALL REINFORCING TO CONFORM TO LATEST CSA STANDARD G30.18, Fy = 400 MPa.

INSTALLATION:

- 5) PLACE 19 mm (³/₄") CLEAR STONE BEDDING ON UNDISTURBED SOIL CAPABLE OF SUSTAINING 175 kPa AND COMPACT TO 98% STANDARD PROCTOR DENSITY.
- 6) EXCAVATION SHALL BE BACKFILLED WITH UNSHRINKABLE FILL TO WITHIN 100 MM (4") FROM FINISHED GRADE. BACKFILL THE REMAINING 100 MM (4") TO FINISHED GRADE AS PER TORONTO HYDRO CIVIL SPECIFICATION CV-CON-01.
- 7) FOR VEHICULAR TRAFFIC REFER TO GUARD POSTS (BOLLARDS) STD. 31-4080.
- 8) PAD-MOUNT LOCATION SHALL BE KEPT CLEAR OF OBSTRUCTIONS FOR ACCESS BY TORONTO HYDRO PERSONNEL AND EQUIPMENT.
- 9) UNUSED CABLE ENTRY DUCTS SHALL BE PLUGGED WITH DUCT PLUGS AND PARGED PRIOR TO BACKFILLING.
- 10) CONTRACTOR SHALL PLUG GROUNDING HOLES AND PARGED PRIOR TO BACKFILLING. CONTRACTOR SHALL PLUG TOP SLAB LIFTING ANCHOR OPENINGS WITH CAULKING PRIOR TO PLACEMENT OF TRANSFORMER.
- 11) PRECAST UNITS SHALL BE DELIVERED BY CRANE-EQUIPPED TRUCKS. EXCAVATION SHALL BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK. MINIMUM OVERHEAD CLEARANCE OF 5500 mm (18'-0") IS REQUIRED. CONTRACTOR SHALL ASSIST SUPPLIER IN LOWERING THE PRECAST UNITS INTO EXCAVATION.
- 12) CUSTOMER TO PROVIDE 3000 mm (10'-0") OF FLAT LEVEL GROUND SURFACE ON OPERATING SIDE (IN-FRONT) OF TRANSFORMER FOR OPERATIONAL NEEDS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
C. P. / G. D. 2002-07-11

Scale:
N. T. S.


Rev: 16

31-4030


3/3

PAD-MOUNTS
THREE PHASE PRECAST PAD-MOUNT
1830 mm (6'-0") x 1830 mm (6'-0")





PLAN VIEW



SECTION 'A-A'

BILL OF MATERIALS FOR 31-4050			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY A
1	FOUNDATION PAD 1980 mm x 2160 mm x 1350 mm DEEP	3540024	1
2	STRIP FOOTING (FLOOR) 2130 mm x 2310 mm x 200 mm, 300 mm WIDE	9656481	1
ASSOCIATED STANDARDS			
3	GROUNDING REQUIREMENTS	STD. 18-5500	1

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction




Approved By:
B. D. 2020-09-25

Drafted By: B. D.
Designed By: B. D.

Original Issue:
G. D. /C.P. 2002-07-11


PAD-MOUNTS
THREE PHASE PMH 9/11 SWITCHGEAR
1980 mm x 2160 mm x 1350 mm

Scale: N. T. S. Rev: 15 31-4050 1/2



PAD DETAIL

* DOORS TO BE ON LONGER SIDES



**WALL REINFORCEMENT
DETAIL 'A'**

NOTES:

MATERIALS:

- 1) CONCRETE SHALL HAVE A MIN. 28-DAY COMPRESSIVE STRENGTH OF 35 MPa. CONCRETE PRODUCTION AND PLACEMENT SHALL CONFORM TO LATEST CSA-A23.1. ALL TESTING SHALL CONFORM TO LATEST CSA-A23.2.
- 2) MANUFACTURER SHALL ADD DATE OF MANUFACTURE STAMP ON ALL PRECAST UNITS.
- 3) EXPOSURE CLASSIFICATION TO FREEZING AND THAWING IN A SATURATED CONDITION BUT WITH NO CHLORIDES SHALL BE F-1.
- 4) ALL REINFORCING TO CONFORM TO LATEST CSA STANDARD G30.18, Fy = 400 MPa.
- 5) CONCRETE COVER ON PRECAST STRIP FOOTING SHALL BE 50 mm (2"), ALL OTHERS SHALL BE 30 mm (1 1/4"). ALL EXPOSED EDGES SHALL HAVE 25 mm (1") CHAMFER.
- 6) PROVIDE 90° STANDARD HOOK FOR WALL HORIZONTAL REINFORCING BARS.
- 7) 4 - 13 mm (1/2") THREADED INSERTS FOR TRANSFORMER MOUNTING SHALL BE ADDED. THE INSERTS TO BE PLUGGED BY THE MANUFACTURER TO PREVENT ENTRY OF FOREIGN MATTER DURING TRANSIT.
- 8) LIFTING HOLES CAN BE INSTALLED IN FOUNDATION WALLS FOR MANUFACTURER'S LIFTING PREFERENCE. IN ADDITION, 4-LIFTING ANCHORS FOR LIFTING PURPOSES SHALL BE PROVIDED ON THE INSIDE OF ALL FOUNDATION WALLS AND ON TOP OF STRIP FOOTING AS SHOWN IN THIS STANDARD. LIFTING ANCHORS SHALL BE GALVANIZED. LIFTING ANCHORS SHALL BE CAPABLE OF LIFTING THE PRECAST UNITS AND THIS SHALL BE CERTIFIED BY MANUFACTURER'S PROFESSIONAL ENGINEER.

INSTALLATION:

- 9) PLACE 19 mm (3/4") CLEAR STONE BEDDING ON UNDISTURBED SOIL CAPABLE OF SUSTAINING 75 kPa AND COMPACT TO 98% STANDARD PROCTOR DENSITY.
- 10) EXCAVATION SHALL BE BACKFILLED TO FINISHED GRADE AS PER TORONTO HYDRO CIVIL SPECIFICATION CV-CON-01 CLAUSE 5.1.17 AND/OR CITY OF TORONTO'S LATEST BACKFILLING REQUIREMENT.
- 11) TORONTO HYDRO INSPECTOR SHALL BE PRESENT DURING THE INSTALLATION, 24-HOUR NOTICE IS REQUIRED PRIOR TO STARTING THE INSTALLATION.
- 12) FOR VEHICULAR TRAFFIC REFER TO GUARD POSTS (BOLLARDS) STD. 31-4080.
- 13) PAD-MOUNT LOCATION SHALL BE KEPT CLEAR OF OBSTRUCTIONS FOR ACCESS BY TORONTO HYDRO PERSONNEL AND EQUIPMENT.
- 14) UNUSED CABLE ENTRY DUCTS SHALL BE PLUGGED WITH DUCT PLUGS AND PARGED PRIOR TO BACKFILLING.
- 15) CONTRACTOR TO PLUG ALL HOLES (LIFTING AND GROUNDING) AND PARGED PRIOR TO BACKFILLING.
- 16) PRECAST UNITS ARE DELIVERED BY CRANE-EQUIPPED TRUCKS. EXCAVATION MUST BE READY, SAFE AND ACCESSIBLE FOR UNLOADING FROM THE REAR OF THE TRUCK. MIN. OVERHEAD CLEARANCE OF 5.5 m (18'-0") IS REQUIRED. CONTRACTOR SHALL ASSIST SUPPLIER IN LOWERING THE UNITS INTO EXCAVATION.
- 17) WHEN LOCATING PAD-MOUNT, A 3.0 m (10'-0") AREA OF FLAT GROUND SURFACE IS REQUIRED INFRONT OF THE OPERATING SIDE (DOOR SIDE) OF TRANSFORMER FOR OPERATIONAL NEEDS.
- 18) THE FOUNDATION SHALL BE ORIENTED WITH THE LONG SIDE (DOOR SIDE OF SWITCHGEAR) PARALLEL TO THE CURB. FOR SCADA-OPERATED SWITCHGEARS ENSURE THAT LOW VOLTAGE AND SWITCHING COMPARTMENTS ARE NOT IN CONFLICT WITH VEHICULAR AND PEDESTRIAN TRAFFIC.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2020-09-25

Drafted By: B.D.
Designed By: B.D.

Original Issue:
G.D./C.P. 2002-07-11


Scale:
N.T.S.

Rev: 15

31-4050


2/2

**PAD-MOUNTS
THREE PHASE PMH 9/11 SWITCHGEAR
1980 mm x 2160 mm x 1350 mm**




DETAIL 'A' - PLAN VIEW

SEE NOTE 2A




DETAIL 'B' - PLAN VIEW

SEE NOTE 2B




DETAIL 'C' - PLAN VIEW

SEE NOTE 2C



DETAIL 'D' - PLAN VIEW

SEE NOTE 2C



DETAIL 'E' - SECTION VIEW

SINGLE PHASE PADMOUNT TRANSFORMER, LINE OF SIGHT

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2022-01-31

Drafted By:
J.D.

Designed By:
B.D.

Original Issue:
G.D./L.G. 2004-11-30

Scale:
N.T.S.

Rev:


5

31-4070

1/2

**PADMOUNT TRANSFORMERS
WITHOUT INTERNAL CURRENT LIMITING FUSE AND
PRESSURE RELIEF DEVICE**





△ DETAIL 'F' - SECTION VIEW

THREE PHASE PADMOUNT TRANSFORMER, LINE OF SIGHT

NOTES:

- △ 1) PADMOUNT TRANSFORMERS WITH AN INTERNAL CURRENT LIMITING FUSE AND PRESSURE RELIEF DEVICE SHALL FOLLOW CLEARANCES AS SPECIFIED IN STD 31-4100. THIS SHALL APPLY TO ALL NEW PADMOUNT TRANSFORMERS.
- △ 2) PADMOUNT TRANSFORMERS WITHOUT AN INTERNAL CURRENT LIMITING FUSE AND PRESSURE RELIEF DEVICE (WHICH INCLUDES ALL LEGACY PADMOUNT TRANSFORMERS) SHALL FOLLOW CLEARANCES AS SPECIFIED IN THIS STANDARD:
 - A) 6000 mm (20'-0") FROM ANY DOOR, WINDOW OR VENTILATION INLET/OUTLET OPENING, OR
 - B) 3000 mm (10'-0") FROM ANY COMBUSTIBLE WALL, SURFACE OR MATERIAL ON A BUILDING, OR
 - C) IF 3A AND 3B CANNOT BE MET, A BARRIER WITH NON-COMBUSTIBLE SURFACE OR MATERIAL IS CONSTRUCTED BETWEEN THE TRANSFORMER AND ANY DOOR, WINDOW, VENTILATION INLET/OUTLET OPENING.
- △ 3) NON-COMBUSTIBLE BARRIER SURFACE OR MATERIAL SHALL PROVIDE A MINIMUM OF 3 HOUR FIRE RATING.
- △ 4) NON-COMBUSTIBLE BARRIER SURFACE OR MATERIAL SHALL EXTEND TO A PROJECTION LINE FURTHEST FROM THE CORNER OF THE TRANSFORMER AS PER DETAILS 'E' AND 'F'.
- △ 5) NON-COMBUSTIBLE BARRIER SHALL BE DESIGNED AND INSTALLED BY CUSTOMER.
- △ 6) NON-COMBUSTIBLE BARRIER WALL SHALL BE REINFORCED CONCRETE, BRICK OR CONCRETE BLOCK.
- 7) REFERENCE RULE 26-242 ONTARIO ELECTRICAL SAFETY CODE.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2022-01-31

Drafted By:
J.D.

Designed By:
B.D.

Original Issue:
G.D./L.G. 2004-11-30

Scale:
N.T.S.

Rev:


5

31-4070

2/2

**PADMOUNT TRANSFORMERS
WITHOUT INTERNAL CURRENT LIMITING FUSE AND
PRESSURE RELIEF DEVICE**





△ PAD-MOUNT ELEVATION VIEW

NOTES:

- 1) INSTALL GUARD POSTS (BOLLARDS) IF THE EQUIPMENT IS LESS THAN 1000 mm (3'-4") FROM THE CURB OR ANYWHERE TORONTO HYDRO DEEMS NECESSARY.
- △ 2) NUMBER OF GUARD POSTS AND LOCATIONS SHOWN ARE TYPICAL ARRANGEMENTS. ACTUAL NUMBER OF GUARD POSTS AND LOCATIONS SHALL BE DETERMINED BY TORONTO HYDRO DESIGNER OR INSPECTOR, USING THE FOLLOWING CRITERIA:
 - A) GUARD POST INSTALLATIONS SHALL ALLOW EQUIPMENT DOORS TO BE OPENED THROUGH THEIR FULL RANGE.
 - B) DISTANCE BETWEEN GUARD POSTS AND OUTSIDE EDGE OF THE PAD-MOUNT SHALL BE AS INDICATED IN THIS STANDARD UNLESS OTHERWISE NOTED.
 - C) GUARD POST INSTALLATIONS SHALL ALLOW TORONTO HYDRO PERSONNEL UNIMPEDED ACCESS TO THE EQUIPMENT.
 - D) THE MAX. DISTANCE BETWEEN TWO GUARD POSTS SHALL BE AS INDICATED IN THIS STANDARD.
- 3) BACKFILL REMAINING EXCAVATION AND COMPACT AS PER CIVIL SPECIFICATION CV-CON-01.
- 4) FILL GUARD POSTS WITH 20 MPa CONCRETE.
- 5) PAINT GUARD POST WITH SAFETY YELLOW PAINT. FOR PROPER ADHESION OF PAINT, GUARD POST SHALL BE CLEANED AND PRIMED PRIOR TO PAINTING. A REFLECTIVE STRIP IF REQUIRED SHALL BE PLACED AT EACH POST.
- 6) ALL GUARD POSTS SHALL BE GROUNDED. REFER TO STD. 18-5000 FOR GROUNDING DETAILS. REFER TO STANDARDS 31-4020, 31-4030, 31-4050 FOR PAD-MOUNT CIVIL DETAILS.
- △ 7) CONTRACTOR TO INSTALL A CONSTRUCTION JOINT AROUND THE GUARD POSTS EXCEPT IN GRASSY BOULEVARDS.
- △ 8) CYLINDER TUBE SIZES:
 - 200 mm (8") FOR 100 mm (4") AND 125 mm (5") GUARD POST
 - 250 mm (10") FOR 150 mm (6") GUARD POST
- △ 9) USE 100 mm (4") GUARD POSTS FOR 1-PHASE PADS AND 125 mm (5") OR 150 mm (6") FOR 3-PHASE AND SWITCHGEAR PADS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**PAD-MOUNTS
GUARD POSTS (BOLLARDS)**



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
G. D. / L. G. 2000-12-19




Scale:
N. T. S.

Rev:

9

31-4080

1/3



NOTES:

- 1) ANY AND ALL OBJECTS WITHIN THE CLEARANCE ZONE AREA, ARE SUBJECT TO REMOVAL WITHOUT ANY PRIOR NOTICE SHOULD OPERATIONAL OR EMERGENCY CONDITIONS EXIST.
- 2) TORONTO HYDRO SHALL NOT BE HELD RESPONSIBLE FOR ANY COSTS ASSOCIATED WITH THE REMOVAL OR RESULTING DAMAGE TO ANY OBJECTS WITHIN THE CLEARANCE ZONE AREA. THE DEVELOPER/OWNER ASSUMES ALL RESPONSIBILITY FOR ENCRDACHING WITHIN THE CLEARANCE ZONE AREA.
- 3) FINAL FINISHED GRADE WITHIN CLEARANCE ZONE SHALL NOT BE ALTERED.
- 4) IN CASES WHERE THE DESIGN REQUIRES A VALUE LESS THAN THE SPECIFIED LIMITATION, CONTACT STANDARDS AND MATERIALS FOR APPROVAL PRIOR TO IMPLEMENTATION.
- 5) REFER TO STANDARD 31-4080 GUARD POSTS (BOLLARDS) PLACEMENT FOR DETAILS.
- 6) REFER TO STANDARD 18-5500 FOR PAD-MOUNTED EQUIPMENT GROUNDING DETAILS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:

Drafted By:
J. D.

Designed By:
B. D.

Original Issue:
B. D. 2019-08-26


**PAD-MOUNTS
CLEARANCE ZONE**

Scale:
N. T. S.

Rev:
1

31-4100


1/1



PLAN VIEW

GENERAL VAULT LAYOUT

SECONDARY DUCTS OR COLLECTOR BUS SEE NOTE 5 FOR COLLECTOR BUS INFORMATION



SECTION 'A-A'

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

ABOVE GRADE - WALK-IN VAULT



Approved By:
B.D. 2018-09-04

Drafted By:
B.D.

Designed By:
B.D.




Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.

Rev: 9

31-6020

1/4



DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES
ABOVE GRADE - WALK-IN VAULT



Approved By:
B.D. 2018-09-04

Drafted By:
B.D.

Designed By:
B.D.

Original Issue:
C.P. 2003-11-27


Scale:
N.T.S.

Rev:

9


31-6020

2/4



DETAIL 'A'

DOOR AND GROUNDING DETAIL



DETAIL 'B'

DOOR PAD BOLT
250 mm (10") BOLT

ABOVE GRADE - WALK-IN VAULT SIZES

TYPE	TX. RATING	L	W	DOORS	ELECTRICAL EQUIPMENT
1	UP TO 2000 kVA	8000 (26'-3")	6000 (19'-8")	1200x2400 HIGH (4' X 8')	REFER TO STANDARDS 13-7030 TO 13-7500
2	2500 kVA TO 4000 kVA ⚠	10000 (32'-0")	8000 (26'-3")	1200x3000 HIGH (4' X 10')	



ABOVE GRADE - WALK-IN VAULT MIN. LOADING (SUSPENDED SLAB)

TYPE	TX. RATING	ROOM AREA	DEAD LOAD (EQUIP. W/ S.F. 1.2)	LIVE LOAD (OBC)
1	UP TO 2000 kVA	48 m ²	9,600 kg	3.6 kPa*
2	2500 kVA TO 4000 kVA	80 m ²	26,500 kg	3.6 kPa*

*FOR VAULT TYPE #1 WITH 48 m² ROOM AREA, THE MINIMUM LIVE LOAD WOULD BE 18,000 kg

*FOR VAULT TYPE #2 WITH 80 m² ROOM AREA, THE MINIMUM LIVE LOAD WOULD BE 30,000 kg

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

ABOVE GRADE - WALK-IN VAULT



Approved By:
B.D. 2018-09-04

Drafted By:
B.D.

Designed By:
B.D.

Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.

Rev:
9

31-6020

3/4

NOTES:

- 1) THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE TORONTO HYDRO REQUIREMENTS FOR THE DESIGN AND CONSTRUCTION OF CUSTOMER-OWNED STRUCTURES DOCUMENT.
- 2) EMERGENCY DOOR IS REQUIRED IN NEW TRANSFORMER VAULTS, LOCATION OF WHICH SHALL BE APPROVED BY TORONTO HYDRO REPRESENTATIVE. EMERGENCY DOOR SHALL HAVE PANIC HARDWARE INSTALLED TO ALLOW DOOR TO OPEN FROM THE INSIDE. THERE SHALL BE NO METHOD OF OPENING AN EMERGENCY DOOR FROM THE OUTSIDE.
- 3) LOCATION OF ELECTRICAL LIGHT FIXTURE CAN BE INSTALLED AS SHOWN OR AN ALTERNATE LOCATION CAN BE CHOSEN PROVIDED ADEQUATE SPACE AND CLEARANCE IS PROVIDED TO ALLOW FOR PROPER OPERATION AND MAINTENANCE OF ELECTRICAL EQUIPMENT.
- 4) DOORS, LOUVER, SECURITY BARS AND ANY METAL PRODUCT SHALL BE GROUNDED BY CONNECTING 2/0 FLEX STRANDED COPPER TO THE GROUNDING LOOP. CONNECTION SHALL BE BY USING PARALLEL GROOVE CLAMPS AND GROUNDING LUG.
- 5) FOR ADJACENT ELECTRICAL ROOMS, COLLECTOR BUSES OR BUS STUBS CAN BE INSTALLED INSTEAD OF DUCTS AT A MINIMUM HEIGHT OF 2134 mm (7'-0") ABOVE FINISHED FLOOR WITH 600 mm (1'-11⁵/₈") CLEARANCE ON EITHER SIDE TO ALLOW PROPER TERMINATION OF CABLES. COLLECTOR BUS TO BE INSTALLED AS PER SECTION 13 AND ALLOW PROPER UNHINDERED OPERATION AND ACCESS OF EQUIPMENT. SEE STD. 15-1500 FOR COLLECTOR BUS DETAILS.
- ⚠ 6) FOR SUSPENDED SLAB DESIGN, DEFINED LOAD CAPACITY IS TO BE A MINIMUM. THE VAULT DESIGN MUST COMPLY WITH THE MOST RECENT VERSION OF THE ONTARIO BUILDING CODE (OBC) AND BE SEALED BY A PROFESSIONAL ENGINEER OF ONTARIO. INCREASED CAPACITY MAY BE REQUIRED DEPENDING ON EXTERNAL FACTORS OR JOINT USE EQUIPMENT ROOMS.
- ⚠ 7) ALL LISTED KVA RATINGS ARE AGGREGATED.
- ⚠ 8) SAFETY FACTOR (S.F.) OF 1.2 SHALL BE ASSUMED IN THE DEAD LOAD CALCULATIONS
- ⚠ 9) FOR SCENARIOS WITH TRANSFORMER CAPACITY GREATER THAN 4 MVA, CUSTOMER TO ATTAIN EQUIPMENT SHOP DRAWINGS AND DETERMINE THE REQUIRED LOADING OUTSIDE OF THE LISTED REQUIREMENTS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES
ABOVE GRADE - WALK-IN VAULT



Approved By:
B.D. 2018-09-04

Drafted By:
B.D.

Designed By:
B.D.


Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.

Rev: 9

31-6020


4/4



PLAN VIEW

NATURAL CROSS-VENTILATION

OUTLET VENT AREA WITH GRATES ON TOP (GRATES TO BE BOLTED DOWN).




SECTION 'A-A'

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CUSTOMER-OWNED STRUCTURES
BELOW-GRADE WALK-IN VAULT**


	Approved By:					
	Drafted By: B. D.	Designed By: B. D.	Original Issue: C. P. 2003-11-27	Scale: N. T. S.	Rev: 11	31-6030



PLAN VIEW

ALTERNATIVE VENTILATION

SECONDARY DUCTS



SECTION 'B-B'

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

BELOW-GRADE WALK-IN VAULT



Approved By:

Drafted By:
B. D.

Designed By:
B. D.


Original Issue:
C. P. 2003-11-27

Scale:
N. T. S.


Rev:
11

31-6030

2/4




SECTION 'C-C'



DETAIL 'A'

DOOR AND GROUNDING DETAIL



DETAIL 'B'

DOOR PAD BOLT

250 mm (10'') BOLT

⚠ BELOW-GRADE - WALK-IN VAULT SIZES						
TYPE	TX. RATING	L	W	X	DOORS ⚠	ELECTRICAL EQUIPMENT
1	UP TO 2000 kVA	8000 (26'-3")	6000 (19'-8")	1900 (6'-3")	1200x2400 HIGH (4' X 8')	REFER TO STANDARDS 13-7030 TO 13-7500
2	2500 kVA TO 4000 kVA	10000 (32'-0")	8000 (26'-3")	3000 (10'-0")	1200x3000 HIGH (4' X 10')	

⚠ BELOW-GRADE - WALK-IN VAULT MIN. LOADING (SUSPENDED SLAB)				
TYPE	TX. RATING	ROOM AREA	DEAD LOAD (EQUIP. W/ S.F. 1.2)	LIVE LOAD (OBC)
1	UP TO 2000 kVA	48 m ²	9,600 kg	3.6 kPa*
2	2500 kVA TO 4000 kVA	80 m ²	26,500 kg	3.6 kPa*

*FOR VAULT TYPE #1 WITH 48 m² ROOM AREA, THE MINIMUM LIVE LOAD WOULD BE 18,000 kg
 *FOR VAULT TYPE #2 WITH 80 m² ROOM AREA, THE MINIMUM LIVE LOAD WOULD BE 30,000 kg

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

BELOW-GRADE WALK-IN VAULT



Approved By:

Drafted By:
B.D.

Designed By:
B.D.

Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.

Rev: 11

31-6030

3/4

NOTES:

- 1) THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE TORONTO HYDRO REQUIREMENTS FOR THE DESIGN AND CONSTRUCTION OF CUSTOMER-OWNED STRUCTURES DOCUMENT.
- 2) EMERGENCY DOOR IS REQUIRED IN NEW TRANSFORMER VAULTS, LOCATION OF WHICH SHALL BE APPROVED BY TORONTO HYDRO REPRESENTATIVE. EMERGENCY DOOR SHALL HAVE PANIC HARDWARE INSTALLED TO ALLOW DOOR TO OPEN FROM THE INSIDE. THERE SHALL BE NO METHOD OF OPENING AN EMERGENCY DOOR FROM THE OUTSIDE.
- 3) EMERGENCY DOOR SHALL HAVE PANIC HARDWARE INSTALLED TO ALLOW DOOR TO OPEN FROM THE INSIDE. THERE SHALL BE NO METHOD OF OPENING AN EMERGENCY DOOR FROM THE OUTSIDE.
- 4) LOCATION OF ELECTRICAL LIGHT FIXTURE CAN BE INSTALLED AS SHOWN OR AN ALTERNATE LOCATION CAN BE CHOSEN PROVIDED ADEQUATE SPACE AND CLEARANCE IS PROVIDED TO ALLOW FOR PROPER OPERATION AND MAINTENANCE OF ELECTRICAL EQUIPMENT.
- 5) DOORS, LOUVER, SECURITY BARS AND ANY METAL PRODUCT SHALL BE GROUNDED BY CONNECTING 2/0 FLEX STRANDED COPPER TO THE GROUNDING LOOP. CONNECTION SHALL BE BY USING PARALLEL GROOVE CLAMPS AND GROUNDING LUG.
- 6) FOR SUSPENDED SLAB DESIGN, DEFINED LOAD CAPACITY IS TO BE A MINIMUM. THE VAULT DESIGN MUST COMPLY WITH THE MOST RECENT VERSION OF THE ONTARIO BUILDING CODE (OBC) AND BE SEALED BY A PROFESSIONAL ENGINEER OF ONTARIO. INCREASED CAPACITY MAY BE REQUIRED DEPENDING ON EXTERNAL FACTORS OR JOINT USE EQUIPMENT ROOMS.
- 7) ALL LISTED KVA RATINGS ARE AGGREGATED.
- 8) SAFETY FACTOR (S.F.) OF 1.2 SHALL BE ASSUMED IN THE DEAD LOAD CALCULATIONS
- 9) FOR SCENARIOS WITH TRANSFORMER CAPACITY GREATER THAN 4 MVA, CUSTOMER TO ATTAIN EQUIPMENT SHOP DRAWINGS AND DETERMINE THE REQUIRED LOADING OUTSIDE OF THE LISTED REQUIREMENTS.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CUSTOMER-OWNED STRUCTURES
BELOW-GRADE WALK-IN VAULT**



Approved By:

Drafted By:
B.D.

Designed By:
B.D.


Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.


Rev: 11

31-6030

4/4



PLAN VIEW



SECTION 'A-A'

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2020-09-25

Drafted By: B.D.
Designed By: B.D.

CUSTOMER-OWNED STRUCTURES
ABOVE-GRADE WALK-IN OR BELOW GRADE SWITCHING VAULT


Original Issue:
J.D. 2013-02-11

Scale:
N.T.S.


Rev: **3**

31-6035

1/2




SECTION 'B-B'



DETAIL 'A'

DOOR AND GROUNDING DETAIL



DETAIL 'B'

DOOR PAD BOLT

250 mm (10'') BOLT

NOTES:

- 1) THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE TORONTO HYDRO REQUIREMENTS FOR THE DESIGN AND CONSTRUCTION OF CUSTOMER-OWNED STRUCTURES DOCUMENT.
- 2) LIGHTING SHALL BE INSTALLED AS PER CUSTOMER-OWNED STRUCTURES DOCUMENT. LIGHTING SHALL BE LOCATED SO THAT THERE IS ADEQUATE SPACE FOR THE RELAMPING OR MAINTENANCE.
- 3) LOCATION OF ELECTRICAL EQUIPMENT CAN BE INSTALLED AS SHOWN OR AN ALTERNATE LOCATION CAN BE CHOSEN PROVIDED ADEQUATE SPACE AND CLEARANCE IS PROVIDED TO ALLOW FOR PROPER OPERATION AND MAINTENANCE OF ELECTRICAL EQUIPMENT. REFER TO STD. 13-7840 FOR SWITCH DIMENSIONS.
- 4) LOCATION OF INCOMING AND OUTGOING CONDUIT ONLY SHOWN FOR GUIDELINE PURPOSES.
- 5) SWITCH VAULTS DO NOT REQUIRE VENTILATION.
- 6) REFER TO STD. 31-6040 FOR BELOW GRADE VAULT STAIR AND ACCESS WELL DETAILS.
- 7) IF REQUIRED, AN EMERGENCY DOOR CAN BE INSTALLED WITH APPROVAL FROM TORONTO HYDRO.
- 8) EMERGENCY DOOR SHALL HAVE PANIC HARDWARE INSTALLED TO ALLOW DOOR TO OPEN FROM THE INSIDE. THERE SHALL BE NO METHOD OF OPENING AN EMERGENCY DOOR FROM THE OUTSIDE.
- 9) DOORS, LOUVER, SECURITY BARS AND ANY METAL PRODUCT SHALL BE GROUNDED BY CONNECTING #2/0 FLEX STRANDED COPPER TO THE GROUNDING LOOP. CONNECTION SHALL BE BY USING PARALLEL GROOVE CLAMPS AND GROUNDING LUG.
- 10) HEIGHT OF CURB AT EXTERIOR THRESHOLD OF DOOR SHALL BE MINIMUM 150 mm (6'') AND MAXIMUM 200 mm (8'') WHEN FACING EXTERIOR FINISHED GRADE. IF VAULT EXIT IS WITHIN BUILDING, MINIMUM 100 mm (4'') CURB SHALL BE MAINTAINED.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

ABOVE-GRADE WALK-IN OR BELOW GRADE SWITCHING VAULT



Approved By:
B.D. 2020-09-25

Drafted By:
B.D.

Designed By:
B.D.


Original Issue:
J.D. 2013-02-11

Scale:
N.T.S.


Rev:
3

31-6035


2/2




PLAN VIEW
ACCESS WELL COVER ASSEMBLY



SECTION 'A-A'




DETAIL 'B'
HOLD DOWN PLATES



ANCHOR ROD MATERIAL SHALL BE 10M REINFORCING STEEL SPACED AT 1.0 m (3'-4") MAX. COMPLETELY AROUND FRAME.

DETAIL 'A'
ANCHOR ROD



DETAIL 'C'
BOLT PAD FOR STUD AND PENTA-HEAD NUT ⚠

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2019-03-22

Drafted By:
N.H.

Designed By:
B.D.

Original Issue:
G.D./C.P. 2003-11-27

Scale:
N.T.S.


Rev:

4


31-6040

1/2


CUSTOMER-OWNED STRUCTURES
STAIR AND ACCESS WELL DETAIL
FOR BELOW-GRADE VAULTS



DETAIL 'D'
GRATE LIFTING HANDLE




DETAIL 'E'
TYPICAL GRATE LOCKING HASP



WEIGHT 9 lbs/SQ. FT. MAX. ⚠

DETAIL 'F'
TYPICAL GRATING



DETAIL 'G'
SAFETY GRIP STAIR TREAD

NOTES:

- ⚠ 1) ACCESS WELL COVER (GRATINGS AND BEAMS) SHOWN IN THIS STANDARD ARE FOR TYPICAL VAULTS LOCATED IN PEDESTRIAN TRAFFIC ONLY. CUSTOMER'S ENGINEER SHALL BE RESPONSIBLE FOR DESIGN OF OVERALL COVER (GRATINGS AND BEAMS) BASED ON VAULT LOCATION AND LOADING REQUIREMENTS. ALL SHOP DRAWINGS SHALL BE STAMPED BY CUSTOMER'S ENGINEER OR MANUFACTURER PRIOR TO BEING ACCEPTED BY TORONTO HYDRO FOR INSTALLATION.
- 2) ALL METAL COMPONENTS SHALL BE HOT DIPPED GALVANIZED AS PER CSA G-164. CLEANED, PRIMED AND PAINTED AFTER WELDING.
- ⚠ 3) ACCESS WELL SHALL BE COMPLETE WITH STANDARD GRATING TYPE 'BB-6' AS MANUFACTURED BY BORDEN METAL PRODUCTS AS APPROVED EQUIVALENT.
- 4) LOCKING HASPS FOR GRATING SHALL BE SUPPLIED BY OWNER AS PER DIAGRAM. LOCKS SHALL BE SUPPLIED BY TORONTO HYDRO.
- 5) PENTA-HEAD NUTS ARE REQUIRED FOR GRATING.
- 6) BEAM SHALL BE SEATED IN A SUITABLE SADDLE (METAL OR CONCRETE) WITH NO FASTENING DEVICES (BOLTS).
- ⚠ 7) CUSTOMER'S ENGINEER SHALL BE RESPONSIBLE FOR DESIGN OF STAIRS, HANDRAIL AND GUARDS AS PER ONTARIO BUILDING CODE REQUIREMENTS FOR AN EXIT STAIR.
- 8) STAIRS, HANDRAIL AND GUARDS SHALL BE OF ALL METAL CONSTRUCTION WITH WELDED JOINTS AND SHALL BE HOT DIPPED GALVANIZED AS PER CSA SPEC. G-164.
- 9) STAIR TREADS AND LANDING SHALL BE AMICO-ISG SAFETY GRIP GRATING OR APPROVED EQUIVALENT.
- 10) REFER TO STD. 31-6030 FOR ACCESS WELL DETAILS. WIDTH OF GRATING SHALL SUIT THE WIDTH OF ACCESS WELL.
- 11) ALL GRATINGS SHALL BE BOLTED DOWN.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
B.D. 2019-03-22

Drafted By: N.H.
Designed By: B.D.

Original Issue:
G.D./C.P. 2003-11-27

Scale:
N.T.S.


Rev:

4


31-6040

2/2

**CUSTOMER-OWNED STRUCTURES
STAIR AND ACCESS WELL DETAIL
FOR BELOW-GRADE VAULTS**




LOUVER FRONT VIEW



**LOUVER AND SECURITY BARS
CROSS SECTION**

15M
SECURITY BAR
SEE NOTE 5



DETAIL 'A'

NOTES: \triangle

- 1) VAULTS SHALL BE PROVIDED WITH A NATURAL CROSS VENTILATION SYSTEM TO PREVENT THE AMBIENT TEMPERATURE IN THE VAULT FROM EXCEEDING 40 DEG. CELSIUS.
- 2) NET AREA OF VENTILATION OPENINGS (INLET AND OUTLET) SHALL NOT BE LESS THAN 20 cm² (3 in²) PER KVA.
- 3) VENT OPENINGS SHALL HAVE 64 mm (2 1/2") SPACED GABLED DOUBLE LOUVER VENT. CONSTRUCTION SHALL BE OF MINIMUM 16 GAUGE STEEL USING 13 mm (1/2") SQUARE MESH BIRD SCREEN.
- 4) SHOP DRAWINGS SHALL BE REVIEWED AND ACCEPTED BY TORONTO HYDRO BEFORE FABRICATION.
- 5) 15M SECURITY BARS SHALL BE MOUNTED ON WALL, SPACED AT 200 mm (8") CENTERS WITH WELDS AT INTERSECTING POINTS. AS AN ALTERNATIVE, SECURITY BARS CAN BE LAGGED INTO TRANSFORMER VAULT WALL.
- 6) ALL STEEL SHALL BE OF METAL CONSTRUCTION WITH WELDED JOINTS.
- 7) ALL STEEL SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION AS PER CSA G-164.
- 8) LOUVER, SECURITY BARS SHALL BE GROUNDED BY CONNECTING #2/0 FLEX STRANDED COPPER TO THE GROUNDING LOOP. CONNECTION TO THE METAL PRODUCTS SHALL BE BY USING PARALLEL GROOVE CLAMPS AND GROUNDING LUG.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CUSTOMER-OWNED STRUCTURES
LOUVER DETAILS FOR VENT OPENINGS**



Approved By:
J.D. 2014-02-04

Drafted By:
K.H.

Designed By:
J.D.


Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.


Rev:
3

31-6050

1/1



ISOMETRIC VIEW



DETAIL "A"

13 mm (1/2") WELDED WIRE MESH

NOTES: ⚠

- 1) BIRD SCREEN TO BE OF METAL CONSTRUCTION WITH WELDED JOINTS.
- 2) BIRD SCREEN AND ALL MOUNTING TO BE HOT DIPPED GALVANIZED AFTER FABRICATION AS PER CSA G-164.
- 3) SHOP DRAWINGS MUST BE REVIEWED AND ACCEPTED BY TORONTO HYDRO BEFORE FABRICATION.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**CUSTOMER-OWNED STRUCTURES
BIRD SCREEN DETAILS**



Approved By:
J.D. 2013-02-12

Drafted By:
D.L.

Designed By:
J.D.


Original Issue:
C.P. 2003-11-27

Scale:
N.T.S.


Rev: **2**

31-6060

1/1



**PLAN VIEW
ROOM FOR HIGH-VOLTAGE CABLES**



SECTION "A-A"

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

CABLE PULL ROOMS

TYPICAL INSTALLATION OF HIGH AND LOW VOLTAGE CABLES



Approved By:

J.D. 2013-02-11

Drafted By:

D.L.

Designed By:

J.D.

Original Issue:

G.D./C.P. 2004-07-30

Scale:


N.T.S.

Rev:


3

31-6070

1/3



PLAN VIEW
ROOM FOR LOW-VOLTAGE CABLES



SECTION "B-B"

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES

CABLE PULL ROOMS

TYPICAL INSTALLATION OF HIGH AND LOW VOLTAGE CABLES



Approved By:

J.D. 2013-02-11

Drafted By:

D.L.

Designed By:

J.D.

Original Issue:

G.D./C.P.

2004-07-30

Scale:

N.T.S.

Rev:

3

31-6070

2/3

NOTES: A

- 1) WHEN HIGH VOLTAGE PRIMARY CABLES OR LOW VOLTAGE SECONDARY CABLES ARE ROUTED THROUGH THE CABLE PULL ROOM, THE FOLLOWING POINTS ARE TO BE CONSIDERED IN DETERMINING THE CONSTRUCTION REQUIREMENTS AND GENERAL LAYOUT:
 - A) IN ALL CASES, IT SHALL BE POSSIBLE TO MAKE CABLE JOINTS IN THE ROOM.
 - B) JOINTS IN CABLE SHALL BE HORIZONTAL.
 - C) THE WALL ON WHICH THE CABLE JOINT IS TO BE RACKED SHALL BE LONG ENOUGH TO ACCOMMODATE THE JOINT AND TWO CABLE BENDS. THE CABLE JOINT MUST BE AT LEAST 300 mm (1'-0") FROM THE FLOOR.
- 2) THE WALLS OF THE ROOM SHALL BE AT LEAST 2400 mm (8'-0") LONG AND 1800 mm (6'-0") WIDE, AND THE MINIMUM HEADROOM SHALL BE 2400 mm (8'-0"). LARGER DIMENSIONS ARE REQUIRED WHEN:
 - A) STEPS, RAILINGS, COLUMNS ARE LOCATED IN THE "CLEAR" WORKING AREA.
 - B) MORE THAN 2 CIRCUITS ARE INSTALLED.
 - C) CONDUITS ARE LOCATED SUCH THAT THE CABLES SHALL ENCIRCLE THE PULL ROOM. HEADROOM DIMENSIONS TO INCREASE IN SUCH CASES.
- 3) CABLE PULLING EYES ARE TO BE INSTALLED AND LOCATED AS PER STD. 31-8210.
- 4) THE CONDUIT ENTRANCES SHALL BE LOCATED NEAR THE CORNERS OF THE ROOM AND BE AS FAR APART AS POSSIBLE AND SHALL BE OFFSET FROM EACH OTHER. ALSO, THE DUCTS THAT GO TO THE STREET MUST SLOPE AWAY FROM THE PULL ROOM.
- 5) LIGHTING AND DRAINAGE MUST BE PROVIDED BY THE CUSTOMER. LIGHT TO BE LOCATED IN THE CENTER OF ROOM.
- 6) PULL ROOM TO BE EQUIPPED WITH A DOOR AND FRAME HAVING A FIRE RATING OF 1.5 HOURS.
- 7) WHERE POSSIBLE, THE DOORWAY SHALL BE LOCATED OPPOSITE A DUCT FACE AND POSITIONED SO THAT IT DOES NOT INTERFERE WITH JOINTING OR CABLE INSTALLATION.
- 8) PADLOCK HASP TO BE PROVIDED FOR DOOR (OR PROVISION FOR TORONTO HYDRO CYLINDER LOCK - 29 mm (1'-1/4") DIAMETER CYLINDER).
- 9) NO FOREIGN EQUIPMENT OR PIPES ARE ALLOWED IN THE PULL ROOM.
- 10) CABLE RACKS AND ARMS WILL BE SUPPLIED AND INSTALLED BY TORONTO HYDRO AND CHARGED TO THE CUSTOMER.
- 11) 24 HR. ACCESS IS REQUIRED.
- 12) THE ABOVE REQUIREMENTS ARE TO BE SHOWN ON THE CUSTOMER'S DRAWINGS FOR TORONTO HYDRO'S REVIEW AND ACCEPTANCE.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
J.D. 2013-02-11

Drafted By: D.L.
Designed By: J.D.

Original Issue:
G.D./C.P. 2004-07-30

Scale:
N.T.S.

Rev: 3


31-6070

3/3

CUSTOMER-OWNED STRUCTURES


CABLE PULL ROOMS

TYPICAL INSTALLATION OF HIGH AND LOW VOLTAGE CABLES



△ BELOW GRADE - TOP ENTRY

- 13-2010 - 4.16 kV (MAX. 3 - 167 kVA TRANSFORMERS) ELECTRICAL EQUIPMENT LAYOUT
- 13-4020 - 13.8 kV COMPACT RADIAL (MAX. 1000 kVA TRANSFORMER) ELECTRICAL EQUIPMENT LAYOUT
- 13-4040 - 13.8 kV COMPACT LOOP (MAX. 1000 kVA TRANSFORMER) ELECTRICAL EQUIPMENT LAYOUT
- 31-5110 - CIVIL STRUCTURE (PROPOSED) - 3000 x 6700 x 3660 mm (10'-0" x 22'-0" x 12'-0")
- 31-5170 - CIVIL STRUCTURE (EXISTING) - 2290 x 6400 x 3660 mm (7'-6" x 21'-0" x 12'-0")



△ ABOVE GRADE - WALK-IN

- 13-2010 - 4.16 kV (MAX. 3 - 167 kVA TRANSFORMERS) ELECTRICAL EQUIPMENT LAYOUT
- 13-4040 - 13.8 kV COMPACT LOOP (MAX. 2000 kVA TRANSFORMER) ELECTRICAL EQUIPMENT LAYOUT
- CIVIL STRUCTURE - 3000 x 7300 x 3660 mm (10'-0" x 24'-0" x 12'-0")

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

CUSTOMER-OWNED STRUCTURES
4.16 kV - 13.8 kV TRANSFORMER VAULTS



Approved By:
J. D. 2014-02-04

Drafted By:
K. H.

Designed By:
J. D.


Original Issue:
C. P. / G. D 2003-11-27

Scale:
N. T. S.

Rev:
4


31-6080

1/3



⚠ BELOW GRADE - TOP ENTRY

13-4010 - 13.8 kV RADIAL (MAX. 2500 kVA TRANSFORMER) ELECTRICAL EQUIPMENT LAYOUT
 CIVIL STRUCTURE - 3000 x 8530 x 3660 mm (10'-0" x 28'-0" x 12'-0")



2 - 1200 x 3000 mm
 (4'-0" x 10'-0")
 ACCESS DOORS TO
 CUSTOMER'S BUILDING

900 x 2100 mm
 (3'-0" x 7'-0")
 ACCESS DOOR TO
 CUSTOMER'S BUILDING

⚠ ABOVE GRADE - WALK-IN VAULT

13-4010 - 13.8 kV RADIAL (MAX. 2500 kVA TRANSFORMER) ELECTRICAL EQUIPMENT LAYOUT
 13-5010 - 13.8 kV NETWORK (MAX. 2000 kVA TRANSFORMERS)
 CIVIL STRUCTURE - 3000 x 8530 x 3660 mm (10'-0" x 28'-0" x 12'-0")

DISTRIBUTION CONSTRUCTION STANDARD
 Civil Construction

CUSTOMER-OWNED STRUCTURES



4.16 kV - 13.8 kV TRANSFORMER VAULTS



Approved By:
 J.D. 2014-02-04

Drafted By:
 K.H.

Designed By:
 J.D.


Original Issue:
 C.P./G.D. 2003-11-27

Scale:
 N.T.S.

Rev:
4


31-6080

2/3



⚠ BELOW GRADE - TOP ENTRY

13-5010 - 13.8 kV NETWORK (MAX. 2000 kVA TRANSFORMERS) ELECTRICAL EQUIPMENT LAYOUT
 31-5180 - MAX. 750 kVA TRANSFORMERS - 2290 x 6700 x 3660 mm (7'-6" x 22'-0" x 12'-0")



⚠ BELOW GRADE - TOP ENTRY

13-5010 - 13.8 kV NETWORK (MAX. 2000 kVA TRANSFORMERS) ELECTRICAL EQUIPMENT LAYOUT
 31-5130 - MAX. 2000 kVA TRANSFORMERS - 3000 x 8530 x 3660 mm (10'-0" x 28'-0" x 12'-0")

NOTE:

1) THIS DRAWING SHALL BE READ IN CONJUNCTION WITH STD. 31-6000 AND STD. 31-6010.

DISTRIBUTION CONSTRUCTION STANDARD
 Civil Construction

CUSTOMER-OWNED STRUCTURES
4.16 kV - 13.8 kV TRANSFORMER VAULTS



Approved By:
 J.D. 2014-02-04

Drafted By:
 K.H.

Designed By:
 J.D.


Original Issue:
 C.P. /G.D. 2003-11-27

Scale:
 N.T.S.

Rev:
4

31-6080

3/3



BOM LEGEND	
A	CABLE SLING (TO SUPPORT PRIMARY CABLE)

BILL OF MATERIALS FOR 31-7400			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
1	CABLE SLING 6" X 18" REINFORCED WITH 1" NYLON STRAP	9662943	4 *

* 4 SLING SUPPORT PER PRIMARY CABLE

NOTES: ⚠

- 1) TEMPORARY CABLE SUPPORT SHALL BE PROVIDED UNTIL PERMANENT SUPPORT IS INSTALLED IN REBUILD STRUCTURES.
- 2) SUPPORT CAN BE USED ON ALL PRIMARY 4.16, 13.8 AND 27.6 KV CABLES.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**TEMPORARY SUPPORT FOR PRIMARY CABLES
IN REBUILD STRUCTURES**



Approved By:
J.D. 2016-06-02

Drafted By:
M.S.

Designed By:
J.D.


Original Issue:
J.D. 2013-05-31

Scale:
N.T.S.

Rev:
1


31-7400

1/1




**CABLE CHAMBER
PLAN VIEW**

PLAN VIEW



SECTION "A-A"

15 m (49' - 3")
MIN. LENGTH



SECTION "B-B"

NOTES:

- 1) MAXIMUM PULLING FORCE - 40 kN
- 2) MATERIAL IS MILD STEEL, 20 mm (3/4") DIAMETER DEVELOPED LENGTH 775 mm (2'-7").
- 3) ALL PARTS TO BE GALVANIZED IN ACCORDANCE WITH LATEST CSA STD. G-164, $F_u=400 \text{ MPa}$ MIN., $F_y=250 \text{ MPa}$ MIN.

ID #3530112

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
J.D. 2012-11-05

Drafted By:
D.L.

Designed By:
J.D.

Original Issue:
J.D. 2000-12-20


Scale:
N.T.S.

Rev:
2

31-8210


1/1

**MATERIAL FABRICATION
CABLE PULLING LOOP
FOR POURED & PRECAST CONCRETE WALLS**



PLAN VIEW

1.6 mm (1/16") BLACK SHEET IRON,
 50 mm (2") SQ. SPOT WELDED TO BOTTOM
 OF 6 x 45 x 45 (1/4" x 1 3/4" x 1 3/4")
 ANGLE



SECTION 'A-A'

SEE DETAIL 'D'
 2 ANCHORS WELDED
 TO BOTTOM OF ANGLE


ID # 3530022

NOTE:
 1) FRAME SHALL BE GALVANIZED IN ACCORDANCE WITH THE LATEST C.S.A. STANDARD G-164.

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		LADDERWAY GRID FRAME FOR TRANSFORMER VAULT					
Approved By: J.D. 2015-09-21		Original Issue: G.D./L.G. 2002-11-15		Scale: N.T.S.	Rev: 3	31-8320	1/2
Drafted By: K.K.		Designed By: J.D.					




2 mm ($\frac{1}{16}$ ") STEEL,
25 mm (1") SQ.
WELDED OVER HOLE \triangle



13 x 38 x 35 F.I.
($\frac{1}{2}$ " x $1\frac{1}{2}$ " x $1\frac{1}{2}$ ")
WELDED ON ALL
4 SIDES TO
6 x 45 x 45
($\frac{1}{4}$ " x $1\frac{3}{4}$ " x $1\frac{3}{4}$ ")
ANGLE


DETAIL 'A'

22 mm ($\frac{7}{8}$ ") HOLE
DRILLED THROUGH
2 THICKNESSES \triangle




DETAIL 'B'

**DETAILS OF HOUSING
FOR HINGE PIN**



DETAIL 'C'
6 REQUIRED



DETAIL 'D'
2 REQUIRED

DETAIL OF ANCHORS

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**LADDERWAY GRID FRAME
FOR TRANSFORMER VAULT**



Approved By:
J.D. 2015-09-21

Drafted By:
K.K.

Designed By:
J.D.




Original Issue:
G.D./L.G. 2002-11-15

Scale:
N.T.S.

Rev:
3

31-8320

2/2



DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

ALUMINUM LADDERWAY GRID



Approved By:
J.D. 2014-03-19

Drafted By:
S.A.K.

Designed By:
J.D.


Original Issue:
G.D. /C.P. 2002-11-15

Scale:
N.T.S.


Rev:
4

31-8330


2/4




SECTION 'C-C'



SECTION 'D-D'



DETAIL 'C'



DETAIL 'D'

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

ALUMINUM LADDERWAY GRID



Approved By:
J.D. 2014-03-19

Drafted By:
S.A.K.

Designed By:
J.D.

Original Issue:
G.D./C.P. 2002-11-15


Scale:
N.T.S.

Rev:
4

31-8330


3/4

TOP VIEW




DETAIL 'E'

TOP VIEW




DETAIL 'F'

FRONT VIEW



DETAIL 'G'

FRONT VIEW



DETAIL 'H'

NOTES:

- 1) BEARING BAR MATERIAL SHALL BE 6061-T6 ALUMINUM. CROSS BARS SHALL BE NOTCHED AND HYDRAULICALLY PRESSED INTO DOVETAIL SLOTS IN BEARING BARS TO PROVIDE A POSITIVE WEDGED CONNECTION.
- 2) DESIGN SHALL MEET CANADIAN HIGHWAY BRIDGE DESIGN CODE CAN/CSA-S6-06, CL-625-ONT LIVE LOADING.
- 3) HINGE BOLTS, PENTA-HEAD LATCH BOLTS, LATCH PLATE, AND HANDLES SHALL BE 304 MILL FINISH STAINLESS STEEL.
- 4) ALUMINUM GRID FINISH SHALL BE CLEAN ANODIZED TO AA-C22A31 STANDARD.
- 5) ALL STAINLESS STEEL ITEMS SHALL BE INSTALLED AFTER ANODIZING.
- 6) REFER TO STD. 31-8340 FOR ALUMINUM LADDERWAY GRATING GUARD.
- 7) DESIGNED ACCORDING TO STANDARD PRACTICE FOR SAFE WALKING SURFACES, F1637-09 AND CITY OF TORONTO ACCESSIBILITY DESIGN GUIDELINES, LATEST REVISION.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

ALUMINUM LADDERWAY GRID



Approved By:
J.D. 2014-03-19

Drafted By:
S.A.K.

Designed By:
J.D.


Original Issue:
G.D./C.P. 2002-11-15

Scale:
N.T.S.


Rev:
4

31-8330

4/4



GUARD FRONT VIEW ⚠



GUARD SIDE VIEW ⚠

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



STEEL LADDERWAY GRATING GUARD



Approved By:
B.D. 2020-05-15

Drafted By:
A.M.E.

Designed By:
B.D.


Original Issue:
G.D./C.P. 2002-11-15

Scale:
N.T.S.


Rev:
6

31-8340


1/3




GUARD TOP VIEW ⚠




GATE ⚠




DETAIL 'A' ⚠



DETAIL 'B' ⚠



DETAIL 'C' ⚠



DETAIL 'D' ⚠

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

STEEL LADDERWAY GRATING GUARD



Approved By:
B.D. 2020-05-15

Drafted By:
A.M.E.

Designed By:
B.D.


Original Issue:
G.D./C.P. 2002-11-15

Scale:
N.T.S.

Rev: 6

31-8340


2/3



ELEVATION

SECTION

SLIDING KICK BOLT



SLIDING KICK BOLT ASSEMBLY

NOTES:

- 1) GUARD AND GATE TO BE FABRICATED OF 19 mm X 19 mm X 3.2 mm GALVANIZED CARBON STEEL SQUARE TUBING.
- 2) WELD ALL JOINTS.
- 3) WHERE POSSIBLE, DRILL/PUNCH ALL HOLES, WELD ALL HINGES AND GATE STOP FLANGE PRIOR TO GALVANIZING.
- 4) ETCH SURFACE AND APPLY "TIGER DRYLAC COATING" IN "SAFETY ORANGE GL/SM" TO GUARD AND GATE.
- 5) LADDERWAY GRATING GUARD TO BE ORDERED IN COMBINATION WITH ALUMINUM GRATING. LADDERWAY GRATING KIT ITEM ID# 9663631.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

STEEL LADDERWAY GRATING GUARD



Approved By:
B.D. 2020-05-15

Drafted By:
A.M.E.

Designed By:
B.D.


Original Issue:
G.D./C.P. 2002-11-15

Scale:
N.T.S.

Rev:
6

31-8340

3/3



PANEL DETAIL PLAN
ITEM I.D. #9663696

Notes:

1. All dimensions are in millimeters unless noted otherwise.
2. Grid to be galvanized in accordance with latest CSA G-164 standard.
3. Spacer Bars: To be raised 1mm tack weld joints.
4. Load Bars 'B': Weld on one side only at each end.
5. Load Bars 'C': Deep weld at each location.
6. Maximum opening of 13mm between load bars.

BILL OF MATERIAL

DESCRIPTION	QTY.	LENGTH
127 X 4.8mm	2	459
127 X 4.8mm	2	1590
S.B. 'A' 25 X 3.2mm	15	449
L.B. 'B' 76 X 4.8mm	13	1590
L.B. 'C' 127 X 4.8mm	12	1590
WEIGHT 172KG (380LBS)		

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction - Material Fabrication

VAULT EXHAUST VENT GRID:
1600 x 457 x 127mm



Approved By:
J.D. 2011-10-11

Drafted By:
S.P.

Designed By:
J.D.

Original Issue:
G.D. C.P. 2002-11-25


Scale:
N.T.S.

Rev:


2

31-8350


1/1




PANEL DETAIL PLAN
ITEM I.D. #9663691




SECTION A-A



SPACER BAR 'A'



LOAD BAR 'B'



LOAD BAR 'C'

Notes:

1. All dimensions are in millimeters unless noted otherwise.
2. Grid to be galvanized in accordance with latest CSA G-164 standard.
3. Spacer Bars: To be raised 1mm tack weld joints.
4. Load Bars 'B': Weld on one side only at each end.
5. Load Bars 'C': Deep weld at each location.
6. Maximum opening of 13mm between load bars.

BILL OF MATERIAL

DESCRIPTION	QTY.	LENGTH
127 X 4.8mm	2	459
127 X 4.8mm	2	1210
S.B. 'A' 25 X 3.2mm	15	449
L.B. 'B' 76 X 4.8mm	13	1210
L.B. 'C' 127 X 4.8mm	12	1210

WEIGHT 121KG (267LBS)

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction - Material Fabrication



Approved By:
J.D. 2011-10-11

Drafted By: A.S.
Designed By: J.D.

Original Issue:
G.D. C.P. 2002-11-25

Scale:
N.T.S.




Rev:

2

31-8360

1/1

VAULT EXHAUST VENT GRID:
1220 x 457 x 127mm



DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**VAULT
TRANSFORMER VAULT LADDER**



Approved By:
Daniel 2015/11/16

Drafted By: B.W.

Designed By: J.D.


Original Issue:
G.D. 2000-12-19

Scale:
N.T.S.

Rev:
3

31-8390


1/2



NOTES:


- 1) ALL MATERIAL SHALL BE GALVANIZED IN ACCORDANCE WITH CSA-G-164, EXCEPT HINGES WHICH ARE STAINLESS STEEL.
- 2) STEEL ELEMENTS SHALL BE IN ACCORDANCE WITH CAN3-G312.2-M GRADE 260W.
- 3) REBARS SHALL BE IN ACCORDANCE WITH CAN/CSA-G30.19 (R2014) GRADE 400W.
- 4) LOCATION OF LADDER AND DOOR SHALL BE DETERMINED AS PER CONSTRUCTION DRAWING.
- 5) DOOR AND ENCLOSURE ONLY INSTALLED IN VAULTS WITH HEADROOM GREATER THAN 2200 mm (7'-3").
- 6) INDUSTRIAL MESH MOUNTED ON ALL OPEN SIDES OF THE ENCLOSURE.

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		VAULT TRANSFORMER VAULT LADDER			
	Approved By: <i>[Signature]</i> 2015/11/16			Scale:	Rev:
	Drafted By: B. W.	Designed By: J. D.	Original Issue: G. D. 2000-12-19	N. T. S.	3
				31-8390	2/2



PLAN OF SUMP HOLE GRID

△ ID# 3530046



PLAN OF SUMP HOLE FRAME

△ ID# 3530530

SECTION A - A

SECTION B - B

△ NOTES:

- 1) UNIFORM LOADING OF 10 kPa.
- 2) ALL MATERIALS TO BE STEEL WITH $F_u = 400 \text{ MPa}$ MINIMUM AND $F_y = 250 \text{ MPa}$ MINIMUM.
- 3) TO BE GALVANIZED AS PER LATEST EDITION OF CSA STANDARD G-164.
- 4) ALL WELDS TO CONFORM TO LATEST EDITION CSA STANDARD W59.


BILL OF MATERIAL		
GRID		
MATERIAL	LENGTH	QTY.
5 x 38 BAR	611	2 PCS.
5 x 38 BAR	621	1 PC.
5 x 38 BAR	115	1 PC.
5 x 38 BAR	253	2 PCS.
5 x 38 BAR	459	3 PCS.
3 x 25 BAR	605	5 PCS.
3 x 25 BAR	611	2 PCS.
FRAME		
MATERIAL	LENGTH	
45 x 45 x 6 BAR	2642	

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction


VAULT SUMP HOLE GRID & FRAME:

650 mm x 650 mm x 38 mm


	Approved By:					
	J.D.		2012-03-24			
Drafted By:	Designed By:	Original Issue:	Scale:	Rev:		
H.M.	J.D.	G.D.	N.T.S.	1	31-8400	1/1



VAULT TOP VIEW



SECTION 'A-A'



SECTION 'B-B'

BILL OF MATERIALS FOR 31-8410			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
			A
1	FOAM 7/8" DIA. X 850' GAP FILLER FOR VAULT SLABS	9664496	1 \triangle
2	COMPOUND JOINT SEALANT 2 PART 5.7 L CONTAINER GREY IN COLOUR	8940080	1 \triangle

NOTES:

- 1) NEW CONSTRUCTION: CONCRETE JOINT INTERFACES SHALL BE CLEAN, DRY AND FREE OF DUST AND LOOSE MATERIAL. A THOROUGH WIRE BRUSHING OR GRINDING MAY BE REQUIRED. THE PRESENCE OF FORM RELEASE AGENTS, OR OTHER CONTAMINANTS SHALL REQUIRE GRINDING TO EXPOSE SOUND, VIRGIN CONCRETE.
- 2) REMEDIAL APPLICATIONS: ALL PREVIOUS SEALANTS, MASTICS OR JOINT FILLERS SHALL BE REMOVED BY ROUTING OR SAW CUTTING. JOINT INTERFACES SHALL BE GRINDED TO EXPOSE SOUND, VIRGIN CONCRETE.
- 3) SEALANT SUPPORT: FOAM (JOINT BACKING) SHALL BE USED TO CONTROL SEALANT DEPTH. FOAM (JOINT BACKING) SHALL BE ROUND.
- 4) MIXING: IF REQUIRED, THE SEALANT SHALL BE THOROUGHLY MIXED IN ACCORDANCE WITH MANUFACTURER'S DIRECTIONS ON CONTAINER LABEL, BEFORE APPLICATION.
- 5) APPLICATION: THE SEALANT SHALL BE APPLIED DIRECTLY FROM THE CONTAINER INTO JOINTS OR BY STANDARD CAULKING GUN.

\triangle 6) IF EXISTING JOINT IS LARGER THAN THE SPECIFIED 13 mm (1/2"), LARGER GAP FILLERS ARE AVAILABLE: FOAM 1" DIA. GAP FILLER (9664495) AND FOAM 1 1/4" DIA. GAP FILLER (9664494)

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**MATERIAL FABRICATION
CAULKING OF REMOVABLE SLABS**



Approved By:
B.D. 2018-08-31

Drafted By:
U.K.

Designed By:
B.D.


Original Issue:
G.D. /C.P. 2002-11-15

Scale:
N.T.S.

Rev:
4


31-8410

1/1



**LADDERWAY
PLAN VIEW**

PIPE BARRIER EMBEDDED IN PAVED AREA




PIPE BARRIER BOLTED TO ROOF

BILL OF MATERIALS FOR 31-8450			
ITEM NO.	DESCRIPTION	ITEM I.D.	QTY
1	100 mm (4") PIPE	9652745	4


NOTES: ⚠

- 1) PIPE SHALL BE FILLED WITH CONCRETE WHEN INSTALLED.
- 2) PIPE SHALL BE GALVANIZED AND PAINTED YELLOW.
- 3) ALL HARDWARE SHALL BE GALVANIZED IN ACCORDANCE WITH CSA-G-164.

DISTRIBUTION CONSTRUCTION STANDARD Civil Construction		LADDERWAY PIPE BARRIER				
	Approved By: J.D. 2013-11-07		Original Issue: G.D. /C.P. 2002-11-15		Scale: N.T.S.	
	Drafted By: K.H.	Designed By: J.D.			Rev: 1	
			31-8450		1/1	



SECTION SHOWING METHOD OF LIFTING



STEEL BASE PLATE

100 mm (4") x 100 mm (4")
x 2 mm (1/16")

NOTES:

1) ASSEMBLY SHALL BE GALVANIZED IN ACCORDANCE WITH CSA-G-164.

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By: *Daniel* 2016/05/25
Drafted By: D.C.
Designed By: J.D.


MATERIAL FABRICATION	
SLEEVE - LIFTING FOR REMOVABLE CONCRETE SLAB	
Original Issue: G.D. 2002-11-15	Scale: N.T.S. Rev: 2
31-8470	
1/1	

6 x 50 FLAT IRON TO BE OFFSET AT BOTH ENDS TO SIT FLUSH WITH FACE OF ANGLES AND GAL. STEEL

1.6 mm (16 GA.) GAL. STEEL BOLTED WITH M6 x 1 x 25 mm R.H. BOLTS

LOCK COVERED WITH SHEET OF RUBBER 152 x 203 AND FASTENED WITH 25 mm BAND IRON

75 x 75 STAINLESS STEEL BUTT HINGES FASTENED WITH M6 x 1 x 25 mm R.H. BOLTS



SECTION A-A

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction

**MATERIAL FABRICATION
DOOR FOR TRANSFORMER VAULT**



Approved By:
J.D. 2013-11-07

Drafted By: D.L.
Designed By: J.D.


Original Issue:
G.D./L.G. 2002-11-15

Scale:
N.T.S.


Rev:
1

31-8500


1/3



SECTION A-A



DETAIL OF HINGE



SECTION B-B

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
J.D. 2013-11-07

Drafted By: D.L.
Designed By: J.D.

Original Issue:
G.D./L.G. 2002-11-15


Scale:
N.T.S.

Rev: 1

31-8500

2/3

MATERIAL FABRICATION
DOOR FOR TRANSFORMER VAULT



DETAIL OF BOLT

BILL OF MATERIALS	
DESCRIPTION	QTY.
6 mm x 38 mm FLAT IRON	5944 mm
6 mm x 32 mm FLAT IRON	127 mm
6 mm x 50 mm FLAT IRON	705 mm
13 mm ROUND IRON	229 mm
6 mm ROUND IRON	89 mm
6 mm x 25 mm x 25 mm ANGLE IRON	1626 mm
6 mm STEEL PLATE 152 mm x 178 mm	1 PC
3 mm x 13 mm F.I. STRAPS, 95 mm LONG	2 PCS
75 mm x 75 mm HEAVY BUTT HINGES	1 1/2 PR
5 mm x 16 mm R.H. RIVETS	4
1.6 mm GALV. STEEL, 1626 mm x 717 mm	1 PC
M6 x 1 x 25 mm R.H. BOLTS	52
RUBBER SHEET, 152 mm X 203 mm	1 PC
25 mm BAND IRON	152 mm
6 mm F.I. SPACER BLOCKS 38 mm x 75 mm	3 PCS

DISTRIBUTION CONSTRUCTION STANDARD
Civil Construction



Approved By:
J.D. 2013-11-07

Drafted By: D.L.
Designed By: J.D.

Original Issue:
G.D./L.G. 2002-11-15

Scale:
N.T.S.

Rev:

1

31-8500

3/3

MATERIAL FABRICATION DOOR FOR TRANSFORMER VAULT